

STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765)

WELL I.D. # L 01395 START CARD # 1024857

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 6 Name Nutter Corp Address 7211 - A 43rd Ave. City Vancouver State Wa Zip 98661

(2) TYPE OF WORK: [] New Well [] Deepening [] Alteration (repair/recondition) [X] Abandonment

(3) DRILL METHOD: [] Rotary Air [] Rotary Mud [X] Cable [] Auger [] Other

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [X] Irrigation [] Thermal [] Injection [] Livestock [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 620 ft. Explosives used [] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Sacks or pounds. Row 1: cement, 0, 620, 10 sks gell. Row 2: grout, , , 290 sks

How was seal placed: Method [] A [] B [] C [] D [] E [] Other Pressure grout thru 2" Trimie Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 10, 1, 337, .250, [], [], [X], []

(7) PERFORATIONS/SCREENS: Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Includes checkboxes for Perforations and Screens.

(8) WELL TESTS: Minimum testing time is 1 hour. [] Pump [] Bailer [] Air [] Flowing Artesian. Yield gal/min, Drawdown, Drill stem at, Time 1 hr.

Temperature of water, Depth Artesian Flow Found, Was a water analysis done? [] Yes By whom, Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other, Depth of strata:

(9) LOCATION OF WELL by legal description: County Washington Latitude Longitude Township 1 N N or S Range 1 W E or W. WM. Section 17 SE 1/4 NE 1/4 Tax Lot 12800 Lot Block Subdivision Street Address of Well (or nearest address) 14705 NW Springville Rd Portland, Or

(10) STATIC WATER LEVEL: 120 ft. below land surface. Date 12-2-14 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found

Table with columns: From, To, Estimated Flow Rate, SWL

(12) WELL LOG: Ground Elevation

Table with columns: Material, From, To, SWL. Description: Abandoned 10" well 620 ft. deep, pulled pump, pumped cement from 620 ft to 200 ft. Perforated 5 rows 40 ft to 190 ft with Star perforator pumped cement from 200 ft to surface. cut 10" pipe off 12" below ground

RECEIVED BY OWRD RECEIVED BY OWRD DEC 31 2014 FEB 20 2015 SALEM, OR SALEM, OR

Date started 12-2-14 Completed 15-15-14 (unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief. Terry Johnson WWC Number 1321

Signed Terry Johnson Date 12-17-14

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Ron Aspaas WWC Number 1445 Signed Ron Aspaas Date 12-17-14