

WATER WELL REPORT

STATE OF OREGON

RECEIVED

APR 5 1983

State Well No.

2N/4W-5dc

State Permit No.

WATER RESOURCES DEPT.

SALEM, OREGON

(1) OWNER:

Name Barney Vanhook
 Address 101 1st St. 29277
 City Stank State Or

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
 Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
 Cased ☐ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
 Threaded ☐ Welded ☒

6" Diam. from 41 ft. to 42 ft. Gauge 250
 " Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

" " " "

Air test 25 gal./min. with drill stem at 100 ft. 2 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 54 Depth artesian flow encountered ft.

(10) CONSTRUCTION:

Special standards: Yes ☐ No ☒Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 7 sacks

How was cement grout placed? PumpedWas pump installed? no Type HP Depth ft.Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Wash Driller's well number
SW 1/4 Section 5 T. 2N R. 4W W.M.
 Tax Lot # Lot Blk Subdivision

Address at well location:

(12) WATER LEVEL: Completed well.

Depth at which water was first found 100 ft.

Static level 30 ft. below land surface. Date 2-28

Artesian pressure lbs. per square inch. Date

(13) WELL LOG:

Diameter of well below casing 6

Depth drilled 130 ft. Depth of completed well 130 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	2	
Red Clay	2	15	
Brown clay	15	37	
Blue Claystone	37	100	
Broken Claystone	100	120	30
Water Bearing			
Blue Claystone	120	130	30

Work started 2-28 19 83 Completed 2-28 19 83

Date well drilling machine moved off of well 2-28 19 83

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] John J. Russell Date 2-28 19 83
 (Drilling Machine Operator)

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name John J. Russell (Type or print)
 (Person, firm or corporation)

Address Manning Oregon

[Signed] John J. Russell
 (Water Well Contractor)

Contractor's License No. 472 Date 2-28 19 83

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report
 are to be filed with the

WATER RESOURCES DEPARTMENT,

SALEM, OREGON 97310

within 30 days from the date of well completion.

SP*12658-690