

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

WASH 79162
11/18/2020

WELL I.D. LABEL# L 140278
START CARD # 1049877
ORIGINAL LOG #

(1) LAND OWNER
Owner Well I.D.
First Name Last Name
Company EDWARDS MEADOWS HOA
Address PO BOX 33
City HILLSBORO State OR Zip 97123

(2) TYPE OF WORK
New Well Deepening Conversion
Alteration (complete 2a & 10) Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrld
Casing: Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD
Rotary Air Rotary Mud Cable Auger Cable Mud
Reverse Rotary Other

(4) PROPOSED USE
Domestic Irrigation Community
Industrial/ Commercial Livestock Dewatering
Thermal Injection Other

(5) BORE HOLE CONSTRUCTION
Special Standard (Attach copy)
Depth of Completed Well 135.00 ft.

Table with columns: Dia, From, To, Material, From, To, Amt, sacks/lbs. Rows include Bentonite and Cement.

How was seal placed: Method A B C D E
Other POURED INTO ANNULA

Backfill placed from ft. to ft. Material
Filter pack from 66 ft. to 135 ft. Material SAND Size 1C

Explosives used: Yes Type Amount

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount Actual Amount

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrld
Shoe Inside Outside Other Location of shoe(s)
Temp casing Yes Dia From + To

(7) PERFORATIONS/SCREENS
Perforations Method
Screens Type WOUND WIRE Material STAINLESS
Perf/ Casing/ Screen Scrm/slot Slot # of Tele/
Screen Liner Dia From To width length slots pipe size

(8) WELL TESTS: Minimum testing time is 1 hour
Pump Bailer Air Flowing Artesian
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)

Temperature 58 °F Lab analysis Yes By
Water quality concerns? Yes (describe below) TDS amount 108 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County WASHINGTON Twp 1.00 S N/S Range 2.00 W E/W WM
Sec 8 SW 1/4 of the NE 1/4 Tax Lot 700
Tax Map Number Lot
Lat " or 45.50010454 DMS or DD
Long " or -122.95758834 DMS or DD
Street address of well Nearest address
2474 SE MEADOW LARK DR. HILLSBORO, OR 97124

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration
Completed Well 11/17/2020 5
Flowing Artesian? Dry Hole?

WATER BEARING ZONES
Depth water was first found 81.00
SWL Date From To Est Flow SWL(psi) + SWL(ft)
11/17/2020 81 131 40 5

(11) WELL LOG
Ground Elevation
Material From To
BROWN CLAY 0 7
SOFT GRAY SILTY SANDY CLAY 7 23
LIGHT GRAY CLAY 23 77
SOFT DARK GRAY CLAY W OCC SANDY STRE 77 109
FINE TO COARSE BLACK SAND 109 118
STICKY BLUE GRAY CLAY 118 124
BROWN SANDY CLAY W BROWN SAND STREA 124 130
STICKY LIGHT GRAY CLAY 130 135

Date Started 11/10/2020 Completed 11/17/2020

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number 1266 Date 11/18/2020
Signed ROY JANNSEN (E-filed)

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 2023 Date 11/18/2020
Signed MICHAEL APPLEBEE (E-filed)
Contact Info (optional) ALPINE RESOURCES LLC 503-647-2969