

STATE OF OREGON
WATER SUPPLY WELL REPORT

WASH 83806

WELL I.D. LABEL# L

Page 1 of 3

START CARD #

ORIGINAL LOG #

160322

1082913

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/12/2026

(1) LAND OWNER

Owner Well I.D.

First Name ANDY

Last Name LANDAUER

Company

Address 34270 NW HORNECKER RD

City HILLSBORO

State OR

Zip 97123

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 135.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
12	0	5	Bentonite	0	29	24	S
10	5	135	Calculated			12.12	
6	135	150	Cement	29	79	14	S
			Calculated			13.42	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED AND PRODDE

Backfill placed from 135 ft. to 150 ft. Material PEA GRAVEL

Filter pack from 79 ft. to 135 ft. Material SAND Size 1C

Explosives used: ☐ Type Amount

Seal Placement Begin Date 8/5/2026 Begin Time 08 15

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	8	☒	1.5	5	0.250	ST	☒			
C	6	☒	1	89	SDR21	PL	☒			
C	6		129	135	SDR21	PL	☒			

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type SLOTTED Material PVC

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Casing	6	89	129	.02	2	10800	Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	12		65	1
Air	24		80	1

Temperature 62 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 147 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County WASHINGTON Twp 1.00 N N/S Range 3.00 W E/W WM

Sec 26 NW 1/4 of the NW 1/4 Tax Lot 901

Tax Map Number Lot

Lat ° ' " or 45.54542793 DMS or DD

Long ° ' " or -123.02937859 DMS or DD

☒ Street address of well ☐ Nearest address

34270 NW HORNECKER RD, HILLSBORO, OR 97123

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/6/2026			8
Flowing Artesian?		☐	Dry Hole?	
		☐		

WATER BEARING ZONES

Depth water was first found 90.00

SWL Date From To Est Flow SWL (psi) + SWL (ft)

8/6/2026	90	102	24		8

(11) WELL LOG

Ground Elevation 180.77 FT

Material	From	To
BROWN CLAY	0	9
SILTY GRAY CLAY	9	46
SOFT GRAY CLAY	46	70
STICKY GRAY CLAY	70	90
FINE-MED COURSE BLACK SAND W/ OCC WOOD	90	102
SILTY BLUE CLAY OCC GRAVEL	102	129
STICKY GRAY BLUE CLAY	129	150

Construction

Begin Date 8/3/2026 Begin Time 07 08 End Date 8/6/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2054 Date 8/11/2026

Signed MILO APPLEBEE (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 2023 Date 8/11/2026

Signed MICHAEL APPLEBEE (E-filed)

Drilling Company: ALPINE RESOURCES 503-647-2969

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

--

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

WASH 83806

8/12/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.54542793 Datum: WGS84

Longitude: -123.02937859

Township/Range/Section/Quarter-Quarter Section:

WM1.00N3.00W26NWNW

Address of Well:

34270 NW HORNECKER RD, HILLSBORO, OR 97123

Well Label: 160322

Printed: August 11, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

