

#18

WASH 886

WASH 886

W/20/2 bb

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

(START CARD) # 27842

(1) OWNER: Jerry Wilson C/O Ceccacci & Assoc. Well Number: 0215 SW Gibbs Portland, OR 97201

(2) TYPE OF WORK: [X] New Well [] Deepen [] Recondition [] Abandon

(3) DRILL METHOD: [X] Rotary Air [] Rotary Mud [] Cable [] Other

(4) PROPOSED USE: [X] Domestic [] Community [] Industrial [X] Irrigation [] Thermal [] Injection [] Other

(5) BORE HOLE CONSTRUCTION: Depth of Completed Well 540 ft. Explosives used [] [X] Type Amount

Table with columns: HOLE Diameter, From, To, Material, SEAL From, To, Amount sacks or pounds. Row 1: 12, 0, 97, Cement, 0, 97, 86 sk+gel

How was seal placed: Method [X] A [] B [X] C [] D [] E Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 8, +1, 97, .250, XX, [], XX, []

(7) PERFORATIONS/SCREENS: Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. (This section is crossed out with a diagonal line)

(8) WELL TESTS: Minimum testing time is 1 hour. [] Pump [] Bailer [X] Air [] Flowing Artesian. Yield gal/min, Drawdown, Drill stem at, Time.

Temperature of water 53 F Depth Artesian Flow Found Was a water analysis done? [] Yes By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: Washington County IN Latitude 2W Longitude E or W, WM. Township 2 N or S, Range 2W Section 2 NW 1/4 NW 1/4 Tax Lot 1300 Lot Block Subdivision Street Address of Well (or nearest address) Rt. 1, Box 599 Hillsboro, OR 97124

(10) STATIC WATER LEVEL: 192 ft. below land surface. Date 03/22/91 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 445, 540, 300+, 192

(12) WELL LOG: Table with columns: Material, From, To, SWL. Red-brown clay w/rock frag. 0 21 Brown clay & basalt, weathered 21 40 Gray-black basalt, boulders 40 46 Brown clay & basalt, weathered 46 55 Gray-brown basalt, occ soft 55 80 Gray-brown basalt, very broken 80 86 Gray-brown basalt, hard 86 110 Red & Brown basalt, lava & clay 110 136 Gray-black basalt, hard, occ frag 136 268 (well pressure grouted 90-160) Interbed, black basalt & lava 268 285 Black & gray-black basalt, occ. fragments 285 320 Interbed, brown basalt & lava 320 326 Brown & black basalt, broken 326 340 Gray-black basalt, hard 340 445 Gray-black basalt, frac, occ. broken 445 472 Black basalt & lava 472 490 Gray-black basalt, occ broken, streaks 490 540

Date started 03/07/91 Completed 03/22/91

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. WWC Number Signed Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. WWC Number 573 Signed Date 03/25/91



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

RECEIVED BY OWRD

FEB 20 2014

SALEM, OR

Do not complete if the well already has a Well I.D Number.

I. OWNER INFORMATION

Current Owner Name (please print): Wilson Farm
Mailing Address: 22380 NW Meier RD
City: Hillsboro State: OR Zip: 97124
Mailing Address (to send Well I.D.): Windermere c/o Burdean Bartlem 733 NW 20th Ave.
City: Portland State: OR Zip: 97209

II. WELL INFORMATION (Do not complete this section if the well report is attached.)

Township: 1N (North/South) Range: 2W (East/West) Section: 2
Tax Lot: 1300 County: Washington 1/4 1/4
Street Address of Well: 22380 NW Meier RD City: Hillsboro
Owner at time the well was constructed, (if known): Wilson Farm
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Do not complete this section if the well report is attached)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Domestic
Date Well Constructed: 3-22-91 & 8-15-95 Total Well Depth: 655 Casing Diameter: 8"
Other Information: WASH 886 & WASH 13850 - Reservoir Well

SUBMITTED BY (please print): Crow Water Systems - Michael Klobes
PHONE: 503-543-6326 FAX: service@crowwater.com

Send application to Oregon Water Resources Department; 725 Summer St NE, Suite A; Salem, Oregon 97301-1266; fax (503) 986-0902. Applications are processed and Well I.D. Numbers are mailed every Wednesday.

For Official Use Only by the Oregon Water Resources Department:
Received Date: 2-20-14
Well Log Number: WASH 886 + WASH 13850
Well Identification #: L-114138