

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WHEELER 275

WATER WELL REPORT

RECEIVED JUN 5 1968

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

STATE OF OREGON (Please type or print) STATE ENGINEER SALEM OREGON

State Well No. 13/20-5 State Permit No.

(1) OWNER: CRYSTAL SPRINGS Bible Camp Name Christal Springs Bible Camp Address 1/2 MARY Thomas Fossil, Oregon

(11) LOCATION OF WELL: County Wheeler Driller's well number 100 1/4 Section 5 T. 13 R. 20 W.M.

(2) TYPE OF WORK (check): New Well [X] Deepening [] Reconditioning [] Abandon []

Bearing and distance from section or subdivision corner

(3) TYPE OF WELL: Rotary [] Driven [] Cable [] Jetted [] Dug [] Bored [] (4) PROPOSED USE (check): Domestic [X] Industrial [] Municipal [] Irrigation [] Test Well [] Other []

(12) WELL LOG: Diameter of well below casing 6 in Depth drilled 40 ft. Depth of completed well 40 ft.

(5) CASING INSTALLED: Threaded [] Welded [X] 6" Diam. from 0 ft. to 40 ft. Gage 250

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation.

PERFORATIONS: Perforated? [X] Yes [] No Type of perforator used cutting torch Size of perforations 1/16 in. by 12 in. 40 perforations from 20 ft. to 40 ft.

Table with columns: MATERIAL, From, To, SWL. Rows include top soil, gravel, red clay, gravel.

(7) SCREENS: Well screen installed? [] Yes [X] No Manufacturer's Name NONE Type NONE Model No. NONE

(8) WATER LEVEL: Completed well. Static level 2 ft. below land surface Date 5/25/68 Artesian pressure none lbs. per square inch Date

(9) WELL TESTS: Drawdown is amount water level is lowered below static level Was a pump test made? [] Yes [X] No If yes, by whom? gal./min. with ft. drawdown after hrs.

Work started MAY 22 1968 Completed 5/25 1968 Date well drilling machine moved off of well 5/25 1968

Bailer test 20 gal./min. with 20 ft. drawdown after 2 hrs. Artesian flow none g.p.m. Date Temperature of water 48 Was a chemical analysis made? [] Yes [X] No

Drilling Machine Operator's Certification: This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief. (Signed) Archie Fox Date 6/2 1968 (Drilling Machine Operator) Drilling Machine Operator's License No. 389

(10) CONSTRUCTION: Well seal—Material used Bentonite Depth of seal 18 ft. Diameter of well bore to bottom of seal 8 in. Were any loose strata cemented off? [] Yes [X] No Depth Was a drive shoe used? [] Yes [X] No Did any strata contain unusable water? [] Yes [X] No Type of water? depth of strata Method of sealing strata off Was well gravel packed? [X] Yes [] No Size of gravel: 1/4 in. minimum Gravel placed from 18 ft. to 40 ft.

Water Well Contractor's Certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. NAME Archie Fox Well Drilling (Person, firm or corporation) (Type or print) Address 2277 Lincoln Rd. (Signed) Archie Fox (Water Well Contractor) Contractor's License No. 444 Date 6/2 1968