

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

AUG 27 1990

(START CARD) #

23281

(1) OWNER:

Name Mr & Mrs Mark Benoit
Address 6635 N.E. Runway Rd.
City Dayton, OR State OR Zip 97114

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 232 ft.

Explosives used Yes ☐ No ☒ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
11	0	18	Cement	0	18	7 BAGS
6	18	232				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☒ E

☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Casing	Diameter		Gauge	Steel		Plastic	Welded	Threaded
	From	To		From	To			
6	0	18	250			☒	☐	☐
4	0	232				☒	☒	☐

Final location of sheet(s)

(7) PERFORATIONS/SCREENS:

☒ Perforations Method 5/8" circular drill holes
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
132	152		60	5/8" circular		☐	☒
192	232		120	5/8" circular		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
18		232	1 hr.

Temperature of water 57 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Yamhill Latitude _____ Longitude _____
Township 4S N or S, Range 3W E or W, WM.
Section 31 1/4 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 6635 N.E. Runway Rd. Dayton, OR

(10) STATIC WATER LEVEL:

65 ft. below land surface. Date Aug 15 90
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 65 ft 36 p.m

From	To	Estimated Flow Rate	SWL
65	66	36 p.m	65
86	87	56 p.m	
152	153	26 p.m	
210	211	8 c.p.m	

(12) WELL LOG:

Material	From	To	SWL
Topsoil	0	2	
Brown clay	2	6	
Brown decomposed clay	6	10	
Fine Blue Sandstone	10	87	
Fine Blue Shale	87	152	
Hard Blue shale	152	158	
Fine Blue Sandstone with unstable layers	158	232	

Date started Aug 13 90 Completed Aug 15, 90

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____

Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 765

Signed James H. Wilcox Date Aug 21, 90