

16

YAMH 154

YAMH 154

4S/3W/5 ba

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

(START CARD) # 26176

(1) OWNER: Name City of Lafayette Well Number: Address P.O. Box 55 City Lafayette State OR Zip 97127

(2) TYPE OF WORK: [X] New Well [] Deepen [] Recondition [] Abandon

(3) DRILL METHOD [X] Rotary Air [] Rotary Mud [] Cable [] Other

(4) PROPOSED USE: [] Domestic [X] Community [] Industrial [] Irrigation [] Thermal [] Injection [X] Other City well

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No Depth of Completed Well 200 ft. Explosives used [] [X] Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Amount sacks or pounds. Row 1: 10", 0, 73, Cement, 0, 72, 50 sacks

How was seal placed: Method [] A [] B [X] C [] D [] E Backfill placed from 72 ft. to 78 ft. Material cave-in

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6", +2, 78, .250, [X], [], [X], []

(7) PERFORATIONS/SCREENS: [X] Perforations Method Saw [] Screens Type Material

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 138, 198, 1/8x7, 84, [], [X]

(8) WELL TESTS: Minimum testing time is 1 hour [] Pump [] Bailer [X] Air [] Flowing Artesian Yield gal/min Drawdown Drill stem at Time

Temperature of water 55° Depth Artesian Flow Found Was a water analysis done? [] Yes By whom

(9) LOCATION OF WELL by legal description: County Yamhill Latitude Longitude Township 4 S N or S. Range 3 W E or W. WM. Section 5 NE 1/4 NW 1/4 Tax Lot 33321300

(10) STATIC WATER LEVEL: 90 ft. below land surface. Date 11/13/90 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 125, 127, 13

(12) WELL LOG: Ground elevation approx 400'. Table with columns: Material, From, To, SWL. Rows: Topsoil, Clay brown, Basalt fx with clay brown, Basalt brown/grey fractured, Basalt brown hard, Basalt brown seamy fractured, Basalt brown/grey porous, Basalt brown medium hd seamy, Basalt grey/brown fractured, Basalt brown/grey wthrd porous, Basalt brown hd seamy fractured, Clay reddish/brown sticky

Date started 11/6/90 Completed 11/12/90

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well constructor standards. Signed Donald Stadel

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. Signed Paul R. Stadel



Oregon Water Resources Department
 725 Summer Street NE, Suite A
 Salem Oregon 97301
 (503) 986-0900
 www.oregon.gov/owrd

Application for Well ID Number

RECEIVED

JUN 21 2018

OWRD

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): City of Lafayette
 Mailing Address: 486 3rd St.
 City, State, Zip: Lafayette, OR 97127
 Mail Well ID to: SAME AS ABOVE In Care Of (C/O)
 Name & Address: Kenny Janssen; 55 SW Yamhill St., Suite 200
 City, State, Zip: Portland, OR 97204

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 4S (North / South) Range: 3W (East / West) Section: 5 NE 1/4 of the NW 1/4
 Tax Lot (usually last 3-5 numbers of Tax Map #): 33321300 County Yamhill
 GPS Coordinates: Latitude: 45 15' 35.9"; Longitude: -123 04' 51.9" (NAD83)
 Street Address of Well, City: City Watershed
 If the property had a different street address in the past: NA

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Municipal
 Date Well Constructed (or property built): November 1990 Total Well Depth: 200 feet Casing Diameter: 6 inches
 Owner at time the well was constructed (if known): City of Lafayette Well Report # (if known): YAMH 154
 Other Information: Well 8

SUBMITTED BY (please print): GSI Water Solutions, Inc. - Portland
 PHONE: (971) 200-8530 EMAIL &/or FAX: kjanssen@gsiws.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

**Coordinates entered actually place this well in 3 S 3 W Sec 32*

For Official Use Only by the Oregon Water Resources Department:		
Received Date: <u>6-21-18</u>	Well Report Number: <u>YAMH 154</u>	Well Identification #: <u>L-130716</u>