

RECEIVED

YAMH 1820 H

3s/3w/33bd  
34953

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

AUG 17 1992

PAGE 1 1820

(START CARD) #

WATER RESOURCES DEPT.

(1) OWNER: SALEM, OREGON 1321  
Name LAURENT-PERRIER CHAMPAGNE  
Address PO BOX 280  
City DUNDEE State OR Zip 97115

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 235 R.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL			Amount
Diameter	From	To	Material	From	To	sacks or pounds
10	0	38	CEMENT	0	38	12 SAX
6	38	245				

How was seal placed: Method  A  B  C  D  E  
 Other \_\_\_\_\_  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	+2	38	.25	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 4	0	235	160#	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) \_\_\_\_\_

(7) PERFORATIONS/SCREENS: SAW

Perforations Method \_\_\_\_\_  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
195	235	6	80			<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
			1 hr.
25.00		235	

Temperature of Water 53 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County YAMHILL Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 3 S N or S. Range 3 W E or W. WM.  
Section 33 SE 1/4 NW 1/4  
Tax Lot \_\_\_\_\_ Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) APPROX 6700 HILLTOP LN DAYTON, OR

(10) STATIC WATER LEVEL:  
108 ft. below land surface. Date 08/13/92  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 158

From	To	Estimated Flow Rate	SWL
158	181	5	108
210	220	20	108

(12) WELL LOG:  
Ground elevation \_\_\_\_\_

Material	From	To	SWL
TOP SOIL	0	4	
RED CLAY	4	12	
DECAYED BASALT	12	31	
MEDIUM HARD GRAY BASALT	31	158	
LOOSE DECAYED BASALT	158	181	108
MEDIUM GRAY BASALT	181	206	
HARD GRAY BASALT	206	210	
LOOSE/CAVING BASALT	210	220	108
MEDIUM GRAY BASALT	220	235	
TAN AND BLACK ASH	235	236	
SOFT BASALT	236	245	

BLUE WATER DRILLING CO.  
DAYTON, OR. 97114

08/11/92  
08/13/92

Date started \_\_\_\_\_ Completed \_\_\_\_\_  
(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. 1438  
Signed *David S. Payne* WWC Number \_\_\_\_\_ Date 08/13/92

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
Signed *Robert Schelbena* WWC Number 417 Date 8-13-92

**For Official Use Only:**

Received Date: \_\_\_\_\_

County Well Log ID #  
**YAMH 1820**

Well Identification Tag #

**28854**

**RECEIVED**

**WELL IDENTIFICATION APPLICATION FORM**

OCT 19 1998

**BUYER/CURRENT WELL OWNER:**

Name: Foxglove Properties, a Minnesota General Partnership

WATER RESOURCES DEPT.  
SALEM, OREGON

Mailing Address: 1300 SW 5th Avenue

*contact person - Dorothy*

City: Portland State: Or Zip: 97201

Phone: 503 538-7484  
(503) 241-2300

**WELL LOCATION:**

County: Yamhill Owner's Well Number: 1321

Township: 3S N or S, Range: 3W E or W, Section: 33 NW 1/4 1/4

Tax Lot Number: 315 Type of Well: water supply Irrigation monitoring  
Application G-13117

Street Address of Well (if different from above): 6700 Hilltop Lane, Dayton, Oregon

**WELL INFORMATION: (do not complete remainder of application if well log is available)**

Start Card Number: 34953 Approx. Construction Date: 9/14/94

Well Constructor: Blue Water Drilling Company, Dayton, Oregon 97114

Name of Owner at Time of Construction: Laurent Perrier Estates Oregon, Inc.

Well Depth (in feet): 235 Feet Static Water Level (in feet): 108

Diameter of Exposed Well Casing (in inches): 6"

Does this well have a formal water right associated with it? Yes:  No:

If Yes: Application #: G-13117 Permit #: G11841 Certificate #: 1321

Please Return Completed Form to:

**Lisa Juul  
Well Identification Program  
Oregon Water Resources Department  
158 12th Street NE  
Salem, OR 97310**