

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

JUL 25 1975

State Well No.

State Permit No.

35/pw-3 cc

SALEM, OREGON

G-7293

(1) OWNER:

Name Ken KAUFMAN
Address P.O. Box 23501, Tigard Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 115 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Operator
Yield: 25 gal./min. with 175 ft. drawdown after 2 hrs.

" " "

Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water 53° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement Grout
Well sealed from land surface to 115 ft.
Diameter of well bore to bottom of seal 9 in.
Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 23 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Yamhill Driller's well number 453
SW 1/4 SW 1/4 Section 3 T. 38 R. 2W W.M.

Bearing and distance from section or subdivision corner PART
OF TAX LOT 14 & 15

(11) WATER LEVEL: Completed well.

Depth at which water was first found 574-588 ft.

Static level 405 ft. below land surface. Date 6-28-75

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 600 ft. Depth of completed well 600 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Soil	0	2	
Brown Clay	2	38	
Brown Shale	38	104	
Hard Gray Basalt	104	172	
Gray + Brown Basalt	172	194	
Hard Gray Basalt	194	282	
Gray + Brown Basalt	282	296	
Hard Gray Basalt	296	377	
Gray + Brown Basalt	377	392	
Hard Gray Basalt	392	484	
Gray + Brown Basalt	484	490	
Hard Gray Basalt	490	574	
Brown Red Basalt (Water)	574	588	405
Hard Gray Basalt	588	600	

Work started 6-23 1975 Completed 6-28 1975

Date well drilling machine moved off of well 6-28 1975

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Raymond R. Borchers Date 6-28, 1975
(Drilling Machine Operator)

Drilling Machine Operator's License No. 305

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Ray Borchers - Well Drilling
(Person, firm or corporation) (Type or print)

Address RT 3, Box 271A Sherwood, Ore.

[Signed] Raymond R. Borchers
(Water Well Contractor)

Contractor's License No. 404 Date 6-28, 1975