

*116  
YamH  
3848*

**RECEIVED**

**MAR 20 1995**

*3s/3w/27cd*

Start Card # 66616

(1) OWNER: Well No. 1490  
Name PINE RIDGE ASSOCIATION  
Address 5901 SILVERADO ST.  
City NAPA St CA Zip 94558

(2) TYPE OF WORK: NEW WELL  
(3) DRILL METHOD: ROTARY AIR  
(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:  
Special Construction Approval: NO Depth of Compl. Well 390 ft  
Explosives used NO Type Amount  
HOLE SEAL  
Diam. From To Material From To Amount  
10 0 99 BENTONITE 0 3 2 SAX  
6 99 390 CEMENT W/GEL 3 99 18 SAX

Seal placement method C  
Backfill: from ft to ft Material  
Gravel: from ft to ft Size

(6) CASING/LINER:  
Diam. From To Gauge Material Connection  
Casing 6 +1 99 .25 STEEL WELDED  
Liner 4 0 390 160# PLASTIC WELDED  
Final Location of shoe(s) NO SHOE

(7) PERFORATIONS/SCREENS:  
 Perforations Method ELECTRIC SAW  
 Screens Type Material  
Slot Tele/pipe  
From To Size Number Diam. size Casing/liner  
350 390 6" 72 LINER

(8) WELL TESTS: Minimum testing time is 1 hour  
Test type AIR  
Yield GPM Draw-down Drill stem at Time  
41 \_\_\_\_\_ 390 1 hr.  
Temperature of water 52 Depth Artesian Flow Found  
Was water analysis done? NO By whom \_\_\_\_\_  
Reason for water not suitable for use  
Depth of strata 0

(9) LOCATION OF WELL by legal description:  
County YAMHILL Lat. ' ' ' Long. ' ' '  
Township 3 S Range 3 W WM.  
Section 27 SE 1/4 SW 1/4  
Tax Lot 3327 Lot 2700 Block Subdivision  
Street Address of Well (or nearest Address)  
8775 WORDEN HILL RD DUNDEE, OR

(10) STATIC WATER LEVEL:  
125 ft. below land surface. Date 03/08/95  
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:  
Depth at which water was first found 183  
From To Est Flow Rate SWL  
183 193 30 125  
316 319 11 125

(12) WELL LOG:  
Material Ground elevation From To SWL  
TOP SOIL 0 5  
BROWN CLAY 5 12  
DECAYED BASALT 12 75  
GRAY CLAY 75 83  
HARD GRAY BASALT 83 165  
DECAYED BASALT 165 193 125  
MEDIUM GRAY BASALT, SOME DECAV 193 316  
DECAYED BASALT, VESICULAR 316 364 125  
MEDIUM GRAY BASALT, SOME DECAV 364 365  
HARD GRAY BASALT 365 375  
MEDIUM GRAY BASALT 375 390  
DAVE PAYSINGER  
BLUE WATER DRILLING CO.  
DAYTON, OR. 97114  
Date started 03/07/95 Completed 03/08/95

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
Signed *David J. Paysinger* WWC Number 1438  
Date 03/08/95