

RECEIVED

MAY 13 1997

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER: Well No. 1669
Name SCOTT LARSEN
Address 2320 CEMETARY RD
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 260 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
10 0 36 BENTONITE 0 36 12 SAX
6 36 260

Seal placement method POURED/TAMPED
Backfill: from ft to ft Material
Gravel: from ft to ft Size

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +2 36 .25 STEEL WELDED
Liner 4 0 260 SDR26 PLASTIC WELDED
Final Location of shoe(s) NO SHOE

(7) PERFORATIONS/SCREENS:
[X] Perf. Method ELECTRIC SAW
[] Screens Type Material
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
180 200 6" 36 LINDER
240 260 6" 36 LINDER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
9 260 1 hr.
Temperature of water 53 Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. Long.
Township 5 S Range 5 W WM.
Section 19 NW 1/4 NW 1/4
Tax Lot R5519 Lot 1200 Block Subdivision
Street Address of Well (or nearest Address)
18211 SW SUNNYRIDGE SHERIDAN, OR

(10) STATIC WATER LEVEL:
103 ft. below land surface. Date 05/10/97
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 189
From To Est Flow Rate SWL
189 211 7 103
230 236 2 103

(12) WELL LOG:
Ground elevation
Material From To SWL
TOP SOIL 0 1
TAN CLAY 1 20
GRAY CLAYSTONE 20 29
GRAY SANDSTONE, HARD/FINE 29 140
GRAY SILTSTONE 140 189
GRAY SILTSTONE W/COARSE STRATIFICATIONS 189 211 103
GRAY CLAYSTONE 211 230
GRAY SILTSTONE W/COARSE STRATIFICATIONS 230 236 103
GRAY CLAYSTONE, GRADUALLY SOFTER 236 260

DAVE PAYSINGER, BLUE WATER DRILLING CO.
DAYTON, OR. 97114

Date started 05/09/97 Completed 05/10/97

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed WWC Number
Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed WWC Number 1438
Date 05/10/97