

YAMH
51539

YAMH 51539

RECEIVED

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L27234
Start Card # 114751

FEB 16 1999

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER: Well No. 1831
Name DUNDEE HILLS VINEYARD LLC
Address 10425 SW RIVERSIDE DR
City PORTLAND St OR Zip 97219

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 495 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
10 0 58 BENTONITE CHIP 0 50 34 SAX
6 58 495 ANNULAR BACFIL
W/BENTONITE CHI 50 58 4 SAX

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' '
Township 3 S Range 3 W WM.
Section 27 NE 1/4 SW 1/4
Tax Lot 2600 Lot Block Subdivision
Street Address of Well (or nearest Address)
8771 NE WORDEN HILL RD DUNDEE, OR

(10) STATIC WATER LEVEL:
99 ft. below land surface. Date 02/10/99
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 218
From To Est Flow Rate SWL
218 235 19 99
468 482 11 99

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 4
RED CLAY 4 24
YELLOW/TAN CLAY 24 30
BASALT, DECAYED, OCC BROWN CLAY 30 42
BASALT, HARD GRAY 42 79
BASALT, MED BLACK 79 91
BASALT, VERY HARD GRAY 91 218
BASALT, MED BLACK WB 218 235 99
BASALT, MED GRAY 235 242
BASALT, VERY HARD GRAY 242 371
BASALT, MED GRAY, VERY SLIGHT DECAY 371 382
BASALT, VERY HARD GRAY 382 468
BASALT, LOOSE DECAY, MINOR VESICULAR WB 468 482 99
BASALT, VERY HARD GRAY 482 495

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 209-8989
Date started 02/05/99 Completed 02/10/99

Seal placement method POURED/PROBED
Backfill: from _____ ft to _____ ft Material _____
Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +2 58 .25 STEEL WELDED
Liner 4 0 495 SDR26 PLASTIC WELDED
Final Location of shoe(s) NO SHOE

(7) PERFORATIONS/SCREENS:
 Perf. Method ELECTRIC SAW
 Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
455 495 .1X7" 72 _____ LINER

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down at Drill stem Time
19 161 260 1 hr.
21 291 390 1
30 396 495 2
Temperature of water 53 Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David L. Paysinger* WWC Number 1438
Date 02/10/99



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

Do not complete if the well already has a Well I.D Number.

I. OWNER INFORMATION

Current Owner Name (please print): Bill Sweat, Winderlea Wine Company
Mailing Address: 8905 NE Worden Hill Rd
City: Dundee State: OR Zip: 97115
Mailing Address (to send Well I.D.):
City: State: Zip:

II. WELL INFORMATION (Do not complete this section if the well report is attached.)

Township: 3 (North/South) Range: 3 (East/West) Section: 27
Tax Lot: County: Yamhill NE 1/4 SW 1/4
Street Address of Well: 8771 NE Worden Hill Rd City: Dundee
Owner at time the well was constructed, (if known): Dundee Hills Vineyard
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Do not complete this section if the well report is attached)

Use of Well (domestic, irrigation, commercial, industrial, monitoring):
Date Well Constructed: 2/10/1999 Total Well Depth: 495 Casing Diameter: 6
Other Information:

SUBMITTED BY (please print): Marc A Norton
PHONE: 503-986-0841 FAX:

Send application to Oregon Water Resources Department; 725 Summer St NE, Suite A; Salem, Oregon 97301-1266; fax (503) 986-0902. Applications are processed and Well I.D. Numbers are mailed every Wednesday.

For Official Use Only by the Oregon Water Resources Department:
Received Date: Well Log Number: YAMH 51539 Well Identification #: L 101444