

YAMH  
51799

**RECEIVED**

OCT 11 1999

WATER RESOURCES DEPT.  
SALEM, OREGON

(1) OWNER: Well No. 1907  
Name FOX GLOVE PROPERTIES  
Address 14905 23RD AV N.  
City MINNEAPOLIS St MN Zip 55447

(2) TYPE OF WORK: NEW WELL  
(3) DRILL METHOD: ROTARY AIR  
(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:  
Special Construction Approval NO Depth of Compl. Well 237 ft  
Explosives used NO Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL			
Diam.	From To	Material	From To	Amount	
10	0 39	BENTONITE CHIP	0 39	33	SAX
8	39 49	CEMENT W/GEL	39 49	12	SAX
6	49 375				

Seal placement method A AND POURED  
Backfill: from 237 ft to 375 ft Material CLEAN CUTTINGS  
Gravel: from \_\_\_\_\_ ft to \_\_\_\_\_ ft Size \_\_\_\_\_

(6) CASING/LINER:

	Diam.	From To	Gauge	Material	Connection
Casing	6	+1.5 49	.25	STEEL	WELDED
Liner	4	0 237	SDR26	PLASTIC	WELDED

Final Location of shoe(s) 49

(7) PERFORATIONS/SCREENS:  
 Perf. Method ELECTRIC SAW  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
197	237	.1X7"	72			LINER

(8) WELL TESTS: Minimum testing time is 1 hour  
Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
60		300	1 hr.
60		230	4
60		360	1/2

Temperature of water 53 Depth Artesian Flow Found \_\_\_\_\_  
Was water analysis done? NO By whom \_\_\_\_\_  
Reason for water not suitable for use \_\_\_\_\_  
Depth of strata \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County YAMHILL Lat. ' ' ' ' Long. ' ' ' '  
Township 3 S Range 3 W WM.  
Section 33 SE 1/4 NW 1/4  
Tax Lot 316 Lot Block Subdivision  
Street Address of Well (or nearest Address):  
NYA, HILLTOP LANE DAYTON, OR

(10) STATIC WATER LEVEL:  
83 ft. below land surface. Date 09/30/99  
Artesian pressure \_\_\_\_\_ lb per square in. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 141

From	To	Est Flow Rate	SWL
141	241	60	83
_____	_____	_____	_____
_____	_____	_____	_____

(12) WELL LOG:

Material	From	To	SWL
TOP SOIL W/COBBLES	0	3	
LOOSE DECAYED BASALT MIXED W/RED CLAY	3	33	
BASALT, MEDIUM GRAY	33	141	
BASALT, DECAYED/VESICULAR	141	241	83
BASALT, MEDIUM TO HARD GRAY	241	303	
BASALT, MEDIUM W/DECAY	303	341	
BASALT, STEWED AND MIXED WITH SHALE	341	358	
BASALT, HARD GRAY	358	361	
CLAYSTONE, GRAY	361	375	

Ground elevation 905

DAVE PAYSINGER, BLUE WATER DRILLING CO.  
(503) 868-7878

\_\_\_\_\_

Date started 09/27/99 Completed 09/30/99

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David G. Paysinger* WWC Number 1438  
Date 09/30/99