

YAMH
52170

RECEIVED

MAY 30 2000

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER: Well No. 1960
Name YAMHILL VALLEY VINEYARDS
Address 16250 SW OLDSVILLE RD
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: ROTARY AIR
(4) PROPOSED USE: FARM

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO _____ Depth of Compl. Well 141 ft
Explosives used NO _____ Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
10 0 18.5 BENTONITE CHIP 0 18.5 12 SAX
6 18.5 141 _____
Seal placement method POURED/PROBED
Backfill: from _____ ft to _____ ft Material _____
Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:
Casing
Diam. From To Gauge Material Connection
6 +1.5 18.5 .25 STEEL WELDED
Liner
4 0 141 SDR26 PLASTIC WELDED
Final Location of shoe(s) 18.5

(7) PERFORATIONS/SCREENS:
 Perf. Method ELECTRIC SAW
 Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
81 101 .1X7" 36 _____ LINDER
121 141 .1X7" 36 _____ LINDER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
75 _____ 141 1 hr.
75 _____ 121 1/2
Temperature of water 54F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' '
Township 5 S Range 5 W WM.
Section 10 NW 1/4 SE 1/4
Tax Lot 1900 Lot Block Subdivision
Street Address of Well (or nearest Address)
16250 SW OLDSVILLE RD MCMINNVILLE, OR

(10) STATIC WATER LEVEL:
67 ft. below land surface. Date 05/23/00
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 88
From To Est Flow Rate SWL
88 121 75 67

(12) WELL LOG:
Material Ground elevation From To SWL
CLEAN FILL DIRT 0 3
BROWN CLAY 3 11
SANDSTONE, BLUE/GRAY, HARD, FINE 11 88
CLAYSTONE, GREEN/GRAY, HARD MIXED WITH SANDSTONE, BLUE/GRAY HARD COARSE 88 121 67
SANDSTONE, BLUE/GRAY, HARD, FINE 121 141
DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878
Date started 05/23/00 Completed 05/23/00

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David S. Paysinger* WWC Number 1438
Date 05/23/00