

(1) OWNER: Well No. 1998  
Name DAVE GROOTERS  
Address 20500 SW EAGLE POINT RD  
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:  
Special Construction Approval NO \_\_\_\_\_ Depth of Compl. Well 185 ft  
Explosives used NO \_\_\_\_\_ Type \_\_\_\_\_ Amount \_\_\_\_\_  
HOLE SEAL  
Diam. From To Material From To Amount  
10 0 19 BENTONITE CHIP 0 19 12 SAX  
6 19 185 \_\_\_\_\_ \_\_\_\_\_ \_\_\_\_\_

Seal placement method POURED/PROBED  
Backfill: from \_\_\_\_\_ ft to \_\_\_\_\_ ft Material \_\_\_\_\_  
Gravel: from \_\_\_\_\_ ft to \_\_\_\_\_ ft Size \_\_\_\_\_

(6) CASING/LINER:  
Casing Diam. From To Gauge Material Connection  
6 +1 19 .25 STEEL WELDED  
Liner 4 0 185 SDR26 PLASTIC WELDED  
Final Location of shoe(s) 19

(7) PERFORATIONS/SCREENS:  
 Perf. Method ELECTRIC SAW  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_  
Slot Tele/pipe  
From To Size Number Diam. Size Casing/liner  
45 65 .1X7" 36 \_\_\_\_\_ \_\_\_\_\_ LINER  
165 185 .1X7" 36 \_\_\_\_\_ \_\_\_\_\_ LINER

(8) WELL TESTS: Minimum testing time is 1 hour  
Test type AIR  
Yield GPM Draw-down Drill stem at Time  
9 \_\_\_\_\_ 185 1 hr.  
9 \_\_\_\_\_ 185 2  
Temperature of water 54 Depth Artesian Flow Found \_\_\_\_\_  
Was water analysis done? NO By whom \_\_\_\_\_  
Reason for water not suitable for use \_\_\_\_\_  
Depth of strata \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County YAMHILL Lat. ' ' ' Long. ' ' '  
Township 3 S Range 4 W MM.  
Section 24 SW 1/4 SE 1/4  
Tax Lot R3425 Lot 200 Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest Address)  
NYA, NE BAYLISS RD CARLTON, OR

(10) STATIC WATER LEVEL:  
32 ft. below land surface. Date 09/15/00  
Artesian pressure \_\_\_\_\_ lb per square in. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 38  
From To Est Flow Rate SWL  
38 179 9.09 32

(12) WELL LOG:  
Material Ground elevation From To SWL  
TOP SOIL 0 3  
CLAY, RED/BROWN SANDY 3 13  
SANDSTONE, GRAY, COARSE 13 38  
SANDSTONE, GRAY, COARSE, OCC HARD LAYERS 38 179 32  
SILTSTONE, GRAY, SOFT 179 185

DAVE PAYSINGER, BLUE WATER DRILLING CO.  
(503) 868-7878  
Date started 09/15/00 Completed 09/15/00

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
Signed *David P. Paysinger* WWC Number 1438  
Date 09/15/00

**RECEIVED**  
OCT 13 2000

WATER RESOURCES DEPT  
SALEM, OREGON