

(1) OWNER: Well No. 2000
Name DAVE GROOTERS
Address 20500 SW EAGLE POINT RD
City MCMINNVILLE St OR Zip 97128

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' '
Township 3 S Range 4 W WN.
Section 25 NW 1/4 NE 1/4
Tax Lot R3424 Lot 1600 Block Subdivision
Street Address of Well (or nearest Address)
NYA, NE BAYLISS RD CARLTON, OR

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: ROTARY AIR
(4) PROPOSED USE: IRRIGATION

(10) STATIC WATER LEVEL:
24 ft. below land surface. Date 09/18/00
Artesian pressure ___ lb per square in. Date ___

(5) BORE HOLE CONSTRUCTION:

Special Construction	Approval NO	Depth of Compl.	Well	200 ft
Explosives used NO	Type	Amount		
HOLE SEAL				
Diam.	From	To	Material	From To Amount
10	0	19	BENTONITE CHIP	0 19 12 SAX
6	19	200		

(11) WATER BEARING ZONES:

Depth at which water was first found	44		
From	To	Est Flow Rate	SWL
44	51	3-4	24
145	146	2-3	24

Seal placement method POURED/PROBED
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	4	
CLAY, RED/BROWN, SANDY	4	13	
SANDSTONE, GRAY	13	44	
SANDSTONE, HARD/COARSE, SOME FRACTURING	44	51	24
SANDSTONE, HARD/FINE	51	144	
SANDSTONE, VERY HARD/FINE	144	146	24
CLAYSTONE, HARD GRAY	146	161	
SILTSTONE, HARD GRAY	161	181	
CLAYSTONE, SOFT GRAY	181	200	

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	6	+1	19	.25	STEEL	WELDED
Liner	4	0	200	SDR26	PLASTIC	WELDED

Final Location of shoe(s) NO SHOE

(7) PERFORATIONS/SCREENS:

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
40	60	.1X7"	36			LINER
180	200	.1X7"	36			LINER

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878
Date started 09/18/00 Completed 09/18/00

RECEIVED
OCT 13 2000
WATER RESOURCES DEPT
SALEM, OREGON

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
7		200	1 hr.
6		200	2

Temperature of water 54 Depth Artesian Flow Found ___
Was water analysis done? YES By whom OWNER
Reason for water not suitable for use ___
Depth of strata ___

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David A. Paysinger* WWC Number 1438
Date 09/18/00