

RECEIVED

OCT 31 2000

(1) OWNER: Well No. 2015
Name PACIFIC LINERS
Address 7450 PERRYDALE RD
City AMITY St OR Zip 97101

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' ' WATER RESOURCES DEPT
Township 5 S Range 4 W WM. SALEM, OREGON
Section 8 NE 1/4 NE 1/4
Tax Lot 100 Lot Block Subdivision
Street Address of Well (or nearest Address)
NYA, 1ST/CHERRY (WHITESON) AMITY, OR

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: CABLE
(4) PROPOSED USE: IRRIGATION

(10) STATIC WATER LEVEL:
36 ft. below land surface. Date 10/25/00
Artesian pressure _____ lb per square in. Date _____

(5) BORE HOLE CONSTRUCTION:

Special Construction	Approval NO	Depth of Compl.	Well	120 ft		
Explosives used NO	Type	Amount				
	HOLE	SEAL				
Diam.	From	To	Material	From	To	Amount
10	0	120	BENTONITE CHIP	0	23	24 SAX
			CEMENT W/GEL	94	99	3 SAX

(11) WATER BEARING ZONES:

Depth at which water was first found	66		
From	To	Est Flow Rate	SWL
66	94	20	36
99	120	75	36

Seal placement method C AND POURED
Backfill: from 23 ft to 99 ft Material 3/8" PEA ROCK
Gravel: from 99 ft to 120 ft Size 3/8" PEA

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	4	
CLAY, BROWN	4	19	
CLAY, BLUE, DENSE	19	66	
SAND, BLUE/BLACK/FINE	66	68	36
SAND, BROWN/FINE	68	72	36
SAND, BLUE/BLACK/COARSE	72	85	36
SAND, BLACK W/SOME GRAVEL	85	94	36
CLAY, GREEN/DENSE	94	99	
SAND, MEDIUM/ GRAVEL, FINE	99	120	36

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	6	+2	104	.25	STEEL	WELDED
	6	119	120	.25	STEEL	WELDED
Liner						

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878
Date started 10/19/00 Completed 10/25/00

(7) PERFORATIONS/SCREENS:

From	To	Slot Size	Number	Diam.	Size	Casing/liner
104	114	40		6"PIPE	SIZE	CASING
114	119	45		6"PIPE	SIZE	CASING

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(8) WELL TESTS: Minimum testing time is 1 hour
Test type BAILER

Yield GPM	Draw-down	Drill stem at	Time
50	24		1 hr.
50	24		4

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David P. Paysinger* WWC Number 1438
Date 10/25/00

Temperature of water 52F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use TOO LITTLE
Depth of strata 66