

(1) OWNER: Well No. 2034
Name FISHER FARMS LLC
Address 9650 SW HARDEBECK
City GASTON St OR Zip 97119

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: CABLE
(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 195 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
15 0 40 BENTONITE CHIP 0 38 51 SAX
12.5 44 195

Seal placement method POURED/PROBED
Backfill: from ___ ft to ___ ft Material
Gravel: from 38 ft to 195 ft Size 6X9 SAND

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 8 +1 108 .25 STEEL WELDED
8 118 140 .25 STEEL WELDED
8 147 177 .25 STEEL WELDED
8 186 188 .25 STEEL WELDED
8 192 195 .25 STEEL WELDED
2 +1 38.5 SCH40 PLASTIC WELDED
Final Location of shoe(s) NO SHOE, PLATE ON BOTTOM

(7) PERFORATIONS/SCREENS:
[] Perf. Method
[X] Screens Type ALLOY MACHINE Material STAINLESS STEEL
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
108 118 80 8"PIPE SIZE CASING
140 147 60 8"PIPE SIZE CASING
177 186 80 8"PIPE SIZE CASING
188 192 80 8"PIPE SIZE CASING

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down at Drill stem Time
325 Full 194 1 hr.
325 Full 194 9

Temperature of water 53F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' ' Long. ' ' ' '
Township 4 S Range 3 W WM.
Section 19 SE 1/4 NE 1/4
Tax Lot 1100 Lot Block Subdivision
Street Address of Well (or nearest Address)
13665 SE AMITY-DAYTON HWY DAYTON, OR

(10) STATIC WATER LEVEL:
30 ft. below land surface. Date 02/14/01
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 107
From To Est Flow Rate SWL
107 147 150 30
177 192 175 30

(12) WELL LOG:
Ground elevation 160
Material From To SWL
TOP SOIL 0 5
CLAY, BROWN 5 15
CLAY, BLUE/FIRM 15 79
CLAY, BLUE W/SOME FINE SAND 79 89
CLAY, GRAY/BLUE/FIRM 89 107
SAND, FINE/MEDIUM W/FINE GRAVEL WB 107 115 30
CLAY, W/FINE SAND 115 122
SAND, FINE 122 123
CLAY, BLUE 123 136
SAND, W/BLUE CLAY 136 140
SAND, FINE W/SOME FINE GRAVEL WB 140 147 30
CLAY, BLUE/GRAY 147 177
SAND, FINE TO MEDIUM W/FINE GRAVEL WB 177 186 30
CLAY, BLUE W/FINE SAND 186 187
CLAY, BLUE 187 188.5
SAND, FINE TO MEDIUM, CLEAN WB 188.5 192.5 30
CLAY, BLUE 192.5 195
Date started 01/29/01 Completed 02/14/01

(unbor... that
the w... band-
onment... ply
well... in
repor...
Blue Water Drilling Company
16303 SE Wallace Road
Dayton, Oregon 97114
Sign...

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed _____ WWC Number 1438 Date 02/14/01

RECEIVED