

AUG 20 2001

STATE OF OREGON WATER RESOURCES DEPT.  
WATER SUPPLY WELL REPORT SALEM, OREGON  
(as required by ORS 537.765)

WELL I.D. # L. 50191  
START CARD # 139392

Instructions for completing this report are on the last page of this form.

(1) OWNER: Name Mrs. Mas Edward M. McCallen. Well Number \_\_\_\_\_  
Address 4840 Hwy 47  
City McMinnville, OR State OR Zip 97128

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 65 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
14"	0	65	Bentonite	0	23	49 Sacks

How was seal placed: Method  A  B  C  D  E  
 Other Bentonite Bags placed top annulus  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material 3/4" gravel  
Gravel placed from 23 ft. to 65 ft. Size of gravel 3/4" to 1 1/2"

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
8"	0	65	250	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Liner: \_\_\_\_\_

(7) PERFORATIONS/SCREENS:

Perforations Method skill saw  
 Screens Type 1/4" x 12" Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
45	65		96	1/4" x 12	slots	<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing  Artesian

Yield gal/min	Drawdown	Drill stem at	Time
65		65	3 hr.

Temperature of water 53° Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Yamhill Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 45 N or S Range 4W E or W. WM. \_\_\_\_\_  
Section 03 NW 1/4 SE 1/4 \_\_\_\_\_  
Tax Lot 4403 ± of 00400 Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 4840 Hwy 47 McMinnville, OR 97128

(10) STATIC WATER LEVEL:  
0 ft. below land surface. Date Aug 17 2001  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 40 ft.

From	To	Estimated Flow Rate	SWL
40	65	65 gpm	0

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Gravel	0	4	
Brown clay	4	16	
Blue clay	16	40	
Medium Blue Sand			
+ small blue gravel	40	65	0

Concrete Grout of 2 bags placed around for protection pipe! placed for protect pipe, incl. from ultra violet SW Rags.

Date started Aug 16 2001 Completed Aug 17 2001

(bonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.  
WWC Number \_\_\_\_\_  
Signed \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
WWC Number 103  
Signed James H. Wiley Date Aug 17 2001