

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L51942
Start Card # 145248

(1) OWNER: Well No. 2121
Name BOB HEILMAN JR.
Address 2343 KINGS POINTE DR.
City LARGO St FL Zip 33774

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO	Depth of Compl. Well	200 ft
Explosives used NO	Type	Amount
HOLE	SEAL	
Diam.	From	To
10	0	48
6	48	200
Material	From	To
BENTONITE CHIP	0	48
Amount		
31 SAX		

Seal placement method POURED/PROBED

Backfill: from ___ ft to ___ ft Material

Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Diam.	From	To	Gauge	Material	Connection
Casing 6	+1.5	48.5	.25	STEEL	WELDED

Liner	4	0	200	SDR26	PLASTIC	WELDED

Final Location of shoe(s) 48.5

(7) PERFORATIONS/SCREENS:

[X] Perf. Method ELECTRIC SAW

[] Screens Type

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
160	170	.1X7"	18			LINER
180	200	.1X7"	36			LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
41		180	1 hr.
41		200	2

Temperature of water 53F Depth Artesian Flow Found

Was water analysis done? NO By whom

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County YAMHILL Lat. ' ' ' ' Long. ' ' ' '
Township 3 S Range 3 W WM.
Section 30 SW 1/4 SW 1/4
Tax Lot 400 Lot Block Subdivision
Street Address of Well (or nearest Address)
8100 OAK SPRINGS FARM RD CARLTON, OR

(10) STATIC WATER LEVEL: 9

35 ft. below land surface. Date 12/03/01
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found	171
From	To
171	192
Est Flow Rate	41
SWL	35

(12) WELL LOG:

Material	Ground elevation	From	To	SWL
TOP SOIL		0	5	
CLAY, TAN/DENSE		5	21	
SANDSTONE, RED/BROWN/FIRM		21	40	
SANDSTONE, GRAY FINE GRAIN		40	171	
SANDSTONE, HARD GRAY/MEDIUM GRAIN/BROKEN		171	192	35
SANDSTONE, FINE GRAIN GRAY		192	200	

RECEIVED

DEC 27 2001

WATER RESOURCES DEPT.
SALEM, OREGON

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 12/03/01 Completed 12/03/01

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David J. Paysinger* WWC Number 1438
Date 12/03/01