

(1) OWNER: Well No. 2154
Name BUNN'S VILLAGE
Address 2771 NE BUNN RD
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: CABLE

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 121 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
11 0 121 BENTONITE CHIP 0 44 31 SAX

Seal placement method POURED/PROBED
Backfill: from ___ ft to ___ ft Material
Gravel: from 44 ft to 121 ft Size 3/8" PEA

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +1 121 .25 STEEL WELDED

Liner
Final Location of shoe(s) NO SHOE, PLATE ON BOTTOM

(7) PERFORATIONS/SCREENS:
[X] Perf. Method TORCH
[] Screens Type Material
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
89 92 .2X6" 15 CASING
101 111 .2X6" 50 CASING

(8) WELL TESTS: Minimum testing time is 1 hour
Test type BAILER
Yield GPM Draw-down Drill stem at Time
25 26 1 hr.
25 26 4

Temperature of water 54F Depth Artesian Flow Found ___
Was water analysis done? NO By whom ___
Reason for water not suitable for use ___
Depth of strata ___

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' Long. ' ' "
Township 4 S Range 4 W WM.
Section 11 NW 1/4 SW 1/4
Tax Lot 2500 Lot Block Subdivision
Street Address of Well (or nearest Address)
2771 NE BUNN RD MCMINNVILLE, OR

(10) STATIC WATER LEVEL:
29 ft. below land surface. Date 07/18/02
Artesian pressure ___ lb per square in. Date ___

(11) WATER BEARING ZONES:
Depth at which water was first found 61
From To Est Flow Rate SWL
61 117 50+ 29

(12) WELL LOG:
Ground elevation 160
Material From To SWL
TOP SOIL 0 5
CLAY, BROWN 5 28
CLAY, BLUE W/SOME BROWN STREAKS 28 31
CLAY, BLUE 31 54
CLAY, GREEN 54 61
CLAY, GREEN W/SAND, FINE 61 69 29
CLAY, BLUE W/SOME SAND, FINE 69 89 29
SAND, MEDIUM W/SOME FINE GRAVEL 89 91 29
CLAY, W/SOME FINE SAND 91 101 29
SAND, MEDIUM W/SOME FINE GRAVEL 101 107 29
CLAY, W/SOME MEDIUM SAND 107 117 29
CLAY, BLuish/GRAY 117 121

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 07/16/02 Completed 07/18/02

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David S. Paysinger* WWC Number 1438
Date 07/18/02

RECEIVED

AUG 13 2002

WATER RESOURCES DEPT.
SALEM, OREGON