

(1) OWNER: Well No. 2190
Name YAMHILL VALLEY VINEYARDS
Address 16250 SW OLDSVILLE RD
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: ABANDON

(3) DRILL METHOD: OTHER

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 280 ft
Explosives used NO Type _____ Amount _____
HOLE SEAL
Dian. From To Material From To Amount
6 0 280 NA _____

Seal placement method NA
Backfill: from 0 ft to 280 ft Material SEE (12)
Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing _____
Liner _____
Final Location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
[] Perf. Method _____
[] Screens Type _____ Material _____
From To Slot Size Number Dian. Size Casing/liner

(8) WELL TESTS: Minimum testing time is 1 hour
Test type _____
Yield GPM Draw-down Drill stem at Time 1 hr.

Temperature of water NA Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' " Long. ' "
Township 5 S Range 5 W WM.
Section 10 NE 1/4 NW 1/4
Tax Lot 1900 Lot Block Subdivision
Street Address of Well (or nearest Address)
16250 SW OLDSVILLE RD MCMINNVILLE, OR

(10) STATIC WATER LEVEL:
129 ft. below land surface. Date 02/28/03
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found NA
From To Est Flow Rate SWL

(12) WELL LOG:
Material Ground elevation From To SWL
PERMANENT ABANDONMENT OF YAMH7280.
OLD WELL LOCATED DEEP WITHIN ESTABLISHED
VINEYARD ON STEEP HILLSIDE. PVC CASING
IN GOOD CONDITION/BOREHOLE OPEN 280' AND
FREE OF ANY DEBRIS. SWL=129' AND QUIET.
CLEAN GRAVEL BACKFILLED FROM 280' UP TO
180' THROUGH ALL SUSPECTED WBZ.
NEAT CEMENT GROUT PLACED THRU
TREMIE PIPE FROM 180' TO 3' FROM LAND
SURFACE. CASING TRIMMED AT 3'.
CEMENT COVERED WITH NATIVE SOILS.
31 BAGS PORTLAND CEMENT REQUIRED.
ABOVE PROCEDURE DISCUSSED W/WRD STAFF B4
DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 02/28/03 Completed 03/01/03

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Dave Paysinger WWC Number 1438
Date 03/01/03

RECEIVED

MAR 14 2003

WATER RESOURCES DEPT.
SALEM, OREGON