

(1) OWNER: Well No. 2204  
Name TONY SOTER  
Address POB 21  
City OAKVILLE St CA Zip 94562

(2) TYPE OF WORK: RECONDITION

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 261 ft  
Explosives used NO Type Amount  
HOLE SEAL  
Diam. From To Material From To Amount  
NA

Seal placement method NA

Backfill: from 261 ft to 280 ft Material CAVING SLOUGH  
Gravel: from 95 ft to 261 ft Size 6X9 SAND

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection

Liner	Diam.	From	To	SDR	Material	Connection
	4	2	261	SDR26	PLASTIC	WELDED

Final Location of shoe(s)

(7) PERFORATIONS/SCREENS:

[ ] Perf. Method  
[X] Screens Type SLOTTED Material PVC  
Slot Tele/pipe  
From To Size Number Diam. Size Casing/liner  
180 260 30 4" PS LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
60		280	1 hr.
60		260	1

Temperature of water 53F Depth Artesian Flow Found  
Was water analysis done? YES By whom TDS94dp  
Reason for water not suitable for use  
Depth of strata

(9) LOCATION OF WELL by legal description:  
County YAMHILL Lat. ' ' ' ' Long. ' ' ' '  
Township 3 S Range 4 W WM.  
Section 23 SE 1/4 NE 1/4  
Tax Lot 1400 Lot Block Subdivision  
Street Address of Well (or nearest Address)  
NE MINERAL SPRINGS RD CARLTON, OR

(10) STATIC WATER LEVEL:  
74 ft. below land surface. Date 05/12/03  
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:  
Depth at which water was first found  
From To Est Flow Rate SWL

(12) WELL LOG:  
Ground elevation  
Material From To SWL  
REMOVE EXISTING LINER AND REPLACE WITH  
SCREENED LINER AND SAND FILTER PACK.  
CLEANED AND REDEVELOPED WELL W/AIR.  
NO OTHER ALTERATION PERFORMED.

RECEIVED

JUN 06 2003

WATER RESOURCES DEPT  
SALEM, OREGON

DAVE PAYSINGER, BLUE WATER DRILLING CO.  
(503) 868-7878

Date started 05/12/03 Completed 05/12/03

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Dave Paysinger* WWC Number 1438  
Date 05/12/03