


State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

State Well ID L63808
Start Card # 157203



(1) OWNER: Well No. 2218
Name ROCK OF AGES
Address 15600 SW ROCK OF AGES RD
City MCMINNVILLE St OR Zip 97128

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' " Long. ' "
Township 4 S Range 5 W WM.
Section 26 NE 1/4 SW 1/4
Tax Lot 2100 Lot Block Subdivision
Street Address of Well (or nearest Address)
15600 SW ROCK OF AGES RD MCMINNVILLE, OR

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(10) STATIC WATER LEVEL:
26 ft. below land surface. Date 06/26/03
Artesian pressure _____ lb per square in. Date _____

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 136 ft
Explosives used NO Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
10 0 28 BENTONITE CHIP 0 28 22 SAX
6 28 160 _____

(11) WATER BEARING ZONES:
Depth at which water was first found 49
From To Est Flow Rate SWL
49 102 32 26

Seal placement method POURED/PROBED
Backfill: from 136 ft to 160 ft Material CAVING SLOUGH
Gravel: from 28 ft to 136 ft Size 6X9 SAND

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 4
CLAY, STICKY BROWN 4 14
CLAYSTONE, BROWN/WEATHERED 14 21
SANDSTONE, GRAY/FIRM/COARSE GRAIN 21 116 26
CLAYSTONE, DARK GRAY W/SANDSTONE STRATS 116 136
CLAYSTONE, DARK GRAY/SOFTER 136 160

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +2 28 .25 STEEL WELDED

Liner 4 2 56 SDR26 PLASTIC WELDED

Final Location of shoe(s) 28

BOREHOLE CAVED IN FROM 136'- 160'.

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 06/25/03 Completed 06/26/03

(7) PERFORATIONS/SCREENS:
[] Perf. Method _____
[X] Screens Type SLOTTED Material PVC
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
56 136 30 _____ 4" PS _____ LINER

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
32 _____ 160 1 hr.
32 _____ 125 1
32 _____ 115 2

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David P. Paysinger* WWC Number 1438
Date 06/26/03

Temperature of water 54F Depth Artesian Flow Found _____
Was water analysis done? YES By whom BWD
Reason for water not suitable for use _____
Depth of strata _____