

(1) OWNER: Well No. 2276
Name YAMHILL VALLEY VINEYARDS
Address 16250 SW OLDSVILLE RD
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: ~~RECONDITION~~ *Alteration*

(3) DRILL METHOD: NA

(4) PROPOSED USE: FARM

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 128 ft
Explosives used NO Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
_____ NA _____
_____ _____
_____ _____

Seal placement method NA
Backfill: from _____ ft to _____ ft Material
Gravel: from 25 ft to 128 ft Size 6X9 SAND

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing _____

Liner 4 2 88 SDR26 PLASTIC WELDED
Final Location of shoe(s) CAP ON 4" @ 128'

(7) PERFORATIONS/SCREENS:
[] Perf. Method _____
[X] Screens Type MACH SLOT Material PVC
Slot Tele/pipe
From To Size Number Dian. Size Casing/liner
88 128 40 _____ 4" PS _____ LINER
_____ _____
_____ _____

(8) WELL TESTS: Minimum testing time is 1 hour
Test type PUMP
Yield GPM Draw-down Drill stem Time
7 65 _____ 1 hr.
_____ _____
_____ _____

Temperature of water 53F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' '
Township 5 S Range 5 W WM.
Section 10 NW 1/4 SE 1/4
Tax Lot 1900 Lot Block Subdivision
Street Address of Well (or nearest Address)
16250 SW OLDSVILLE RD MCMINNVILLE, OR

(10) STATIC WATER LEVEL:
19 ft. below land surface. Date 04/21/04
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found _____
From To Est Flow Rate SWL

(12) WELL LOG:
Material Ground elevation _____
From To SWL
INSTALL 4" LINER W/SCREEN SECTION AND
SAND PACK SCREEN. ORIGINAL LINER HAD
BEEN REMOVED DUE TO DAMAGE CAUSED BY
OVERHEATED PUMP MOTOR SOMETIME PREVIOUS.
NO OTHER WORK PERFORMED OTHER THAN PUMP
TEST INDICATED IN SECTION (8).

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878
Date started 04/21/04 Completed 04/21/04

(unbonded) Water Well Constructor Certification: I certify that
the work I performed on the construction, alteration, or abandon-
ment of this well is in compliance with Oregon water supply
well construction standards. Materials used and information
reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept respon-
sibility for the construction, alteration, or abandonment work
performed on this well during the construction dates reported
above. All work performed during this time is in compliance
with Oregon water supply well construction standards. This
report is true to the best of my knowledge and belief.
Signed *David A. Paysinger* WWC Number 1438
Date 04/22/04

