

STATE OF OREGON

WATER SUPPLY WELL REPORT  
(as required by ORS 537.760)

SEP 16 2004 21075 YAMH. 53835  
ALLOHA, OR 97006

WELL ID # L 71773  
START CARD # 168399

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER  
Name: GAYLE WILHOIT c/o DAVE B. WELT Well Number #2  
Address P.O. BOX 515  
City DUNDEE State OR Zip 97115

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/condition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 88 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL		Sacks or pounds	
Diameter	From To	Material	From To		
10"	0 30	Bentonite	0 30	25	Sks
6"	30 144				

How was seal placed: Method  A  B  C  D  E  
 Other Poured & Prodded slowly  
Backfill placed from 88 ft to 95 ft. Material Pea Gravel  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1 68	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5"	58 68	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5"	83 88	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used  Inside  Outside  None  
Final location of shoe(s) 68' K-Packer at 58'

(7) PERFORATIONS/SCREENS:

Perforations Method Johnson Screen  
 Screens Type Stainless Material Steel

From	To	Slot size	Number	Diameter	Relief pipe size	Casing	Liner
68	83	.020		5"	Pipe	<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Flowing Time
12		56'	1 1/2 hr
4 1/2		40'	" "

Temperature of water 54°F Depth 56'  
Was a water analysis done?  Yes By whom RECEIVED  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored RECEIVED  
Depth of strata: \_\_\_\_\_  
AUG 03 2004

(9) LOCATION OF WELL by legal description:  
County Yamhill Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 3S N or S Range 3 W E or W. WM.  
Section 14 SE 1/4 NE 1/4  
Tax Lot 4201 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address)  
NR. 13260 N.E. Redhills Rd., Newberg, Or

(10) STATIC WATER LEVEL:  
23 ft. below land surface. Date 7-28-04  
Artesian pressure \_\_\_\_\_ lb. per square inch Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 68

From	To	Estimated Flow Rate	SWL
68	83	12	23'
RECEIVED			
AUG 03 2004			

(12) WELL LOG:

Material	From	To	SWL
Brn cly & boulders	0	5	
Gry brn broken clystone	5	27	
Soft grycly	27	49	
Blue gry sandstone	49	57	
Semi cemented sand & gravel.	57	87	23'
Brn sandy clay	87	98	
Soft sandstone	98	144	
Well was completed to 88'. Hole was abandoned 88' to 144.			
Cement/Bentonite	95	144	8 Sks
Pea Gravel backfill	88	95	

Date started 7-29-04 Completed 7-30-04  
(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.  
Signed Mr. Bigsby WWC Number 1492  
Date 7/30/04

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
Signed [Signature] WWC Number 573  
Date 7/30/04