

(1) OWNER: Well No. 2336
Name CLARENCE AHERIN
Address 18495 MEADOWLAKE RD
City YAMHILL St OR Zip 97148

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 121 ft
Explosives used NO Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
10 0 38 BENTONITE CHIP 0 38 21 SAX
6 38 121 _____

Seal placement method POURED/HYDRATED
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size _____

(6) CASING/LINER:
Casing 6 4 2 38 .25 STEEL WELDED
Liner 4 1 121 SDR26 PLASTIC WELDED

Final Location of shoe(s) 38

(7) PERFORATIONS/SCREENS:
[X] Perf. Method CIRCULAR SAW
[] Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
81 101 .1X7" 40 _____ LINER
111 121 .1X7" 20 _____ LINER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
19 _____ 120 1 hr.

Temperature of water 54F Depth Artesian Flow Found _____
Was water analysis done? YES By whom BLUE
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' " Long. ' ' "
Township 3 S Range 5 W WM.
Section 16 SW 1/4 NE 1/4
Tax Lot 300 Lot Block Subdivision
Street Address of Well (or nearest Address)
18495 MEADOWLAKE RD YAMHILL, OR

(10) STATIC WATER LEVEL:
23 ft. below land surface. Date 11/15/04
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 49
From To Est Flow Rate SWL
49 112 19 23

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 3
CLAY, TAN 3 12
CLAY, RED/BROWN 12 16
CLAYSTONE, GRAY 16 49
SANDSTONE, HARD DARK GRAY, COARSE
W/OCC WHITE FRAGMENTS 49 98 23
SANDSTONE, HARD DARK GRAY
MIXED W/HARD DARK GRAY SILTSTONE 98 112 23
CLAYSTONE, DARK/LIGHT GRAY 112 121

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 11/15/04 Completed 11/15/04

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David H. Paysinger* WWC Number 1438
Date 11/15/04

