

(1) OWNER: Well No. 2351
Name BERNARDS FARM
Address 18755 SW HWY 18
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 128 ft
Explosives used NO Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
10 0 43 BENTONITE CHIP 0 43 21 SAX
6 43 140 _____

Seal placement method POURED/HYDRATED
Backfill: from 128 ft to 140 ft Material CAVING SLOUGH
Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +1.5 43 .25 STEEL WELDED
Liner 4 2 128 .25 PLASTIC WELDED

Final Location of shoe(s) 43

(7) PERFORATIONS/SCREENS:
 Perf. Method CIRCULAR SAW
 Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
88 108 .1X7 40 _____ LINER
118 128 .1X7" 20 _____ LINER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
100 _____ 140 1 hr.
100 _____ 120 1

Temperature of water 53F Depth Artesian Flow Found _____
Was water analysis done? YES By whom TDS125PPM
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' ' Long. ' ' ' '
Township 5 S Range 5 W WM.
Section 21 SE 1/4 SW 1/4
Tax Lot 400 Lot Block Subdivision
Street Address of Well (or nearest Address)
18755 SW HWY 18 MCMINNVILLE, OR

(10) STATIC WATER LEVEL:
9 ft. below land surface. Date 02/23/05
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 105
From To Est Flow Rate SWL
105 140 100 9

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 5
CLAY, BROWN 5 15
CLAY, GRAY 15 25
MARINE ROCK, BROWN COARSE 25 29
MARINE ROCK, GRAY COARSE HARD 29 105
MARINE ROCK, GRAY/GRN/WHI, FRACT/BRKN 105 128 9
MARINE ROCK, GRAY/GREEN W/THIN
GRAY/GREEN CLAY/CLAYSTONE STRATS, LOOSE 128 140 9

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 02/22/05 Completed 02/23/05

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David S. Paysinger* WWC Number 1438
Date 02/24/05