

(1) OWNER: Well No. 2407
Name YOUNGBERG HILL VINEYARDS/INN
Address 10660 YOUNGBERG HILL RD
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 346 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
10 0 38 BENTONITE CHIP 0 38 21 SAX
6 38 346

Seal placement method POURED/PROBED
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:
Casing Diam. From To Gauge Material Connection
6 +2 38 .25 STEEL WELDED
Liner 4 2 346 SDR26 PLASTIC WELDED

Final Location of shoe(s) 38

(7) PERFORATIONS/SCREENS:
 Perf. Method CIRCULAR SAW
 Screens Type Material
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
335 346 .1X7" 22 LINER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
20 346 1 hr.
20 330 1

Temperature of water 53F Depth Artesian Flow Found
Was water analysis done? YES By whom BLUE H2O
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' '
Township 4 S Range 5 W WM.
Section 27 NE 1/4 SW 1/4
Tax Lot 200 Lot Block Subdivision
Street Address of Well (or nearest Address)
10660 SW YOUNGBERG HILL RD MCMINNVILLE, OR

(10) STATIC WATER LEVEL:
235 ft. below land surface. Date 10/05/05
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 268
From To Est Flow Rate SWL
276 321 20 235

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 5
ROCK, BROWN SANDY SOFT 5 15
MARINE ROCK, BLUE/GREEN 15 21
MARINE ROCK, GRAY/BLUE 21 276
MARINE ROCK, GRAY/BLUE COARSER W/FRACS 276 321 235
MARINE ROCK, GRAY/BLUE 321 341
CLAYSTONE, GRAY 341 346

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 10/03/05 Completed 10/05/05

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David M. Paysinger* WWC Number 1438
Date 10/06/05

