

(1) OWNER: Well No. 2423
Name AMITY SCHOOL DIST. #4J
Address PO BOX 138
City AMITY St OR Zip 97101

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: ROTARY AIR
(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO _____ Depth of Compl. Well 90 ft
Explosives used NO _____ Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
10 0 77 BENTONITE CHIP 0 35 39 SAX
6 77 90 _____
Seal placement method POURED/HYDRATED
Backfill: from _____ ft to _____ ft Material _____
Gravel: from 35 ft to 77 ft Size 3/8" PEA

(6) CASING/LINER:
Casing
Diam. From To Gauge Material Connection
6 +3 77 .25 STEEL WELDED
Liner
4 2 70 SDR26 PLASTIC WELDED
Final Location of shoe(s) 77

(7) PERFORATIONS/SCREENS:
[X] Perf. Method DH PERFORATOR
[X] Screens Type MACH SLOT Material SCH 40 PVC
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
70 90 40 _____ 4" PS _____ LINER
65 71 .2X1" 80 _____ CASING

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
50 _____ 90 1 hr.
50 _____ 76 2
Temperature of water 54F Depth Artesian Flow Found _____
Was water analysis done? YES By whom BLUE H2O
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' '
Township 5 S Range 4 W WM.
Section 20 SE 1/4 SE 1/4
Tax Lot 1400 Lot Block Subdivision
Street Address of Well (or nearest Address)
503 OAK ST AMITY, OR

(10) STATIC WATER LEVEL:
7 ft. below land surface. Date 12/14/05
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found SWL
From To Est Flow Rate SWL
SWL 71 50 7

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 5
CLAY, BROWN SILTY 5 18 7
CLAY, BROWN 18 19 7
CLAY, BLUE/GRAY W/OCC SAND 19 54 7
CLAY AND CLAYSTONE, GRAY W/SAND & GRAVEL 54 71 7
CLAYSTONE, GRAY 71 90
DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878
Date started 12/12/05 Completed 12/14/05

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David M. Paysinger* WWC Number 1438
Date 12/17/05

RECEIVED
JAN 05 2006

WATER RESOURCES DEPT
SALEM, OREGON