

YAMH 54957

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L90945
Start Card # 1002037

(1) OWNER: Well No. 2550
Name GARY HASSON
Address 12900 NW MOORES VALLEY RD
City YAMHILL St OR Zip 97148

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: ROTARY AIR
(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 260 ft
Explosives used NO Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
10 0 18.5 BENTONITE CHIP 0 18.5 20 SAX
6 18.5 260 _____
Seal placement method POURED/HYDRATED
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size _____

(6) CASING/LINER:
Casing Diam. From To Gauge Material Connection
6 +1.5 18.5 .25 STEEL WELDED
Liner 4 2 260 SCH40 PLASTIC THREADED
Final Location of shoe(s) 18.5 // SPLINE-LOC LINER

(7) PERFORATIONS/SCREENS:
 Perf. Method CIRCULAR SAW
 Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
60 80 .1X7" 40 _____ LINER
160 180 .1X7" 40 _____ LINER
243 260 .1X7" 34 _____ LINER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
52 _____ 258 1 hr.
52 _____ 240 3
52 _____ 225 2
Temperature of water 53F Depth Artesian Flow Found _____
Was water analysis done? YES By whom BLUE H2O
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' " Long. ' ' "
Township 3 S Range 5 W WM.
Section 12 SE 1/4 NW 1/4
Tax Lot 800 Lot Block Subdivision
Street Address of Well (or nearest Address)
12000 NW MOORES VALLEY RD YAMHILL, OR

(10) STATIC WATER LEVEL:
19 ft. below land surface. Date 09/03/07
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 78
From To Est Flow Rate SWL
78 224 50+ 19

(12) WELL LOG:
Material Ground elevation From To SWL
CLAY, TAN W/SOME SOIL 0 13
CLAYSTONE, STRATIFIED LIGHT/DARK AND HARD/MEDIUM GRAY 13 110
CLAYSTONE, DARK GRAY 110 121
CLAYSTONE, LIGHT GRAY 121 129
CLAYSTONE, DARK GRAY, HARD W/THIN SANDSTONE STRATS 129 224
CLAYSTONE, DARK GRAY 224 260

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878
Date started 08/31/07 Completed 09/03/07

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David A. Paysinger* WWC Number 1438
Date 09/03/07

RECEIVED

SEP 24 2007

WATER RESOURCES DEPT
SALEM, OREGON