

(1) OWNER: Well No. 2588
Name GRAND CRU LLC
Address 2803 ORCHARD AVE
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 232 ft
Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
10	0	28	BENTONITE CHIP	0	28	24 SAX
6	28	232				

Seal placement method POURED/HYDRATED

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection
6		+1	29	.25	STEEL	WELDED

Liner	Diam.	From	To	SCH	Material	Connection
4		12	72	SCH40	PLASTIC	THREADED
4		92	212	SCH40	PLASTIC	THREADED

Final Location of shoe(s) 29, SPLINE-LOC LINER

(7) PERFORATIONS/SCREENS:

[] Perf. Method
[X] Screens Type MACH SLOT Material SCH 40 PVC
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
72 92 40 4" PS LNER
212 232 40 4" PS LNER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
7.5		230	1 hr.
7.5		210	3

Temperature of water 54F Depth Artesian Flow Found

Was water analysis done? YES By whom BLUE H2O

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. 45° 20' 16" Long. 123° 07' 48"
Township 3 S Range 4 W WM.
Section 1 NW 1/4 SW 1/4
Tax Lot 1000 Lot Block Subdivision
Street Address of Well (or nearest Address)
17100 WOODLAND LOOP RD YAMHILL, OR

(10) STATIC WATER LEVEL:

27 ft. below land surface. Date 05/29/08
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 72		Est Flow Rate	SWL
From	To		
72	212	7.5	27

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	3	
CLAY, TAN	3	19	
SANDSTONE, GRAY W/OCC THIN LT GRAY STRAT	19	154	
CLAYSTONE, GRAY W/SILTSTONE STRATS	154	184	
CLAYSTONE, GRAY W/OCC LT GRAY SANDSTONE	184	215	
CLAYSTONE, GRAY	215	232	

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

Date started 05/28/08 Completed 05/29/08

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David A. Paysinger* WWC Number 1438
Date 05/30/08