

**STATE OF OREGON  
WATER SUPPLY WELL REPORT**

(as required by ORS 537.765)

WELL I.D. # L 89083  
START CARD # 198851

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Name Mrs. John Whigley Well Number \_\_\_\_\_  
Address 301 NE Hwy 99W # 256  
City McMinnville, OR State OR Zip 97128

(2) TYPE OF WORK  New Well  
 Deepening  Alteration (repair/recondition)  Abandonment  Conversion

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  Auger  Cable Mud  
 Other \_\_\_\_\_

(4) PROPOSED USE  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION Special Construction:  Yes  No  
Depth of Completed Well 205 ft.  
Explosives used:  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

BORE HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds
1 1/2"	0	38	Concrete	0	38	180 lbs.
6"	38	205				

How was seal placed: Method  A  B  C  D  E  
 Other \_\_\_\_\_  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	12	38	.252	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 4"	3	205	16 gws	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used  Inside  Outside  None  
Final location of shoe(s) \_\_\_\_\_

(7) PERFORATIONS/SCREENS

Perforations Method Electric drill  
 Screens Type 5/8" casing Material \_\_\_\_\_

From	To	Slot Size	Number	Diameter	Yield pipe	Casing	Liner
165	205		180	5/8"	1.66		<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour  
 Pump  Bailor  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
30	25 ft.	205	1 hour
30		Pump set 188	4 hours

Temperature of water 52° Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom Alexia/Myriad  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL (legal description)  
County Yamhill  
Tax Lot 700 Lot \_\_\_\_\_  
Township 55 N or S Range 6W E or W WM  
Section 24 SE 1/4 NW 1/4

Lat \_\_\_\_\_ " or \_\_\_\_\_ (degrees or decimal)  
Long \_\_\_\_\_ " or \_\_\_\_\_ (degrees or decimal)  
Street Address of Well (or nearest address) 18460 Goshu Valley Rd. Shondan, OR 97178

(10) STATIC WATER LEVEL  
128 ft. below land surface. Date Sept 8, 2008  
\_\_\_\_\_ ft. below land surface. Date \_\_\_\_\_  
Artesian pressure \_\_\_\_\_ lb. per square inch Date \_\_\_\_\_

(11) WATER BEARING ZONES

Depth at which water was first found 175'

From	To	Estimated Flow Rate	SWL
175'	176'	350 gpm	128

(12) WELL LOG Ground Elevation Est. 600'

Material	From	To	SWL
Topsoil	0	3	
Black & Yellow loam	3	19	
Red clay	19	28	
Brown decomposed clay	28	31	
Hard Blue Sandstone with unstable layers	31	205	128

Date Started Sept 5, 2008 Completed Sept 8, 2008

(unbonded) Water Well Constructor Certification  
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number \_\_\_\_\_ Date \_\_\_\_\_  
Signed \_\_\_\_\_

(bonded) Water Well Constructor Certification  
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 795 Date Sept 9, 2008  
Signed x Randall R. Wiley

**RECEIVED**  
SEP 10 2008  
ORIGINAL - WATER RESOURCES DEPARTMENT  
FIRST COPY - CONSTRUCTOR  
SECOND COPY - CUSTOMER  
SALEM, OREGON