

YAMH 55399

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L98606
Start Card # 1005920

(1) OWNER: Well No. 2628
Name WASHINGTON ROOFING CO
Address 1700 SW HWY 18
City MCMINNVILLE St OR Zip 97128

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: CABLE
(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 91 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
12 0 91 BENTONITE GRAN 0 6 5 SAX
BENTONITE CHIP 6 21 31 SAX

Seal placement method POURED/HYDRATED
Backfill: from ___ ft to ___ ft Material
Gravel: from 21 ft to 90 ft Size 3/8" PEA

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +1 91 .25 STEEL WELDED
Liner
Final Location of shoe(s) 91

(7) PERFORATIONS/SCREENS:
 Perf. Method TORCH
 Screens Type Material
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
73 89 .2X8" 64 CASING

(8) WELL TESTS: Minimum testing time is 1 hour
Test type BAILER
Yield GPM Draw-down Drill stem at Time
19 34 1 hr.
32.5 54 4
Temperature of water 54F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. 45° 11' 14" Long. 123° 13' 10"
Township 4 S Range 4 W WM.
Section 30 SE 1/4 SE 1/4
Tax Lot 2200 Lot Block Subdivision
Street Address of Well (or nearest Address)
1700 SW HWY 18 MCMINNVILLE, OR

(10) STATIC WATER LEVEL:
6 ft. below land surface. Date 01/14/09
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 6
From To Est Flow Rate SWL
6 91 32 6

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 5
CLAY, BROWN 5 16
CLAY, BLUE 16 48
CLAY, BROWN W/GRIT 48 52
CLAY, BROWN 52 53
CLAY, BLUE W/COARSE SAND AND FINE GRAVEL
STRATIFIED W/THIN CLEAN BLUE CLAY LAYERS 53 64
CLAY, BLUE W/OCC FINE GRAVEL 64 75
CLAY, BROWN W/GRIT 75 78
CLAY, GRAY W/GRIT 78 84
CLAY, BLUE/GRAY 84 91
DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868 7878
Date started 01/05/09 Completed 01/14/09

RECEIVED

FEB 02 2009

WATER RESOURCES DEPT
SALEM, OREGON

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David H. Paysinger* WWC Number 1438
Date 01/17/09