

YAMH 55526

State of Oregon  
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L100552  
Start Card # 1007196

(1) OWNER: Well No. 2661  
Name ARNE GODDIK  
Address 18265 SE NECK RD  
City DAYTON St OR Zip 97114

(9) LOCATION OF WELL by legal description:  
County YAMHILL Lat. ' ' ' Long. ' ' '  
Township 4 S Range 3 W WM.  
Section 10 SE 1/4 SW 1/4  
Tax Lot 1500 Lot Block Subdivision  
Street Address of Well (or nearest Address)  
18265 SE NECK RD DAYTON, OR

(2) TYPE OF WORK: NEW WELL  
(3) DRILL METHOD: CABLE  
(4) PROPOSED USE: IRRIGATION

(10) STATIC WATER LEVEL:  
65 ft. below land surface. Date 08/24/09  
Artesian pressure \_\_\_\_ lb per square in. Date \_\_\_\_

(5) BORE HOLE CONSTRUCTION:  
Special Construction Approval NO Depth of Compl. Well 133 ft  
Explosives used NO Type Amount  
HOLE SEAL  
Diam. From To Material From To Amount  
11 0 133 BENTONITE CHIP 0 25 24 SAX

(11) WATER BEARING ZONES:  
Depth at which water was first found 65  
From To Est Flow Rate SWL  
65 133 40 65

Seal placement method POURED/HYDRATED  
Backfill: from \_\_\_\_ ft to \_\_\_\_ ft Material  
Gravel: from 25 ft to 133 ft Size 3/8" PEA

(12) WELL LOG:  
Material Ground elevation From To SWL  
TOP SOIL 0 5  
CLAY, BROWN 5 22  
CLAY, BLUE 22 46  
CLAY, GRAY W/SOME SAND 46 65  
CLAY, GREEN W/SOME SAND 65 70  
SAND, MED W/SOME CLAY, GREEN 70 85  
CLAY, GREEN/GRAY W/SAND 85 91  
CLAY, GREEN/GRAY 91 96  
CLAY, GREEN/GRAY W/SOME SAND 96 106  
CLAY, GREEN W/SAND AND FINE GRAVEL 106 118  
CLAY, GREEN/BLUE W/SOME SAND 118 125  
CLAY, GRAY 125 133

(6) CASING/LINER:  
Diam. From To Gauge Material Connection  
Casing 6 +2 133 .25 STEEL WELDED  
Liner  
Final Location of shoe(s) 133

DAVE PAYSINGER, BLUE WATER DRILLING CO.  
(503) 868 7878  
Date started 08/17/09 Completed 08/24/09

(7) PERFORATIONS/SCREENS:  
[X] Perf. Method TORCH  
[ ] Screens Type Material  
Slot Tele/pipe  
From To Size Number Diam. Size Casing/liner  
103 133 .1X7" 120 CASING

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(8) WELL TESTS: Minimum testing time is 1 hour  
Test type BAILER  
Yield GPM Draw-down Drill stem at Time  
19 15 1 hr.  
20 16 2  
30 25 6

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
Signed *David A. Paysinger* WWC Number 1438  
Date 08/25/09

RECEIVED  
SEP 21 2009  
WATER RESOURCES DEPT  
SALEM, OREGON