

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L104539
Start Card # 1013366

(1) OWNER: Well No. 2708
Name REVANA FAMILY PARTNERS
Address 5118 TANGLE LN
City HOUSTON St TX Zip 77056

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 299 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
10 0 78 BENTONITE CHIP 0 50 34 SAX
6 78 299 ANNULAR BACFIL
W/BENTONITE CHI 50 78 18 SAX

Seal placement method POURED/PROBED

Backfill: from ___ ft to ___ ft Material

Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	6	+2	78	.25	STEEL	WELDED

	Diam.	From	To	SCH	Material	Connection
Liner	4	18	299	SCH40	PLASTIC	THREADED

Final Location of shoe(s) 78 // SPLINE LOC LINER

(7) PERFORATIONS/SCREENS:

☒ Perf. Method CIRCULAR SAW

☐ Screens Type Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
118	138	.1X5"	24			LINER
158	178	.1X5"	24			LINER
198	238	.1X5"	48			LINER
258	278	.1X7"	38			LINER
288	298	.1X7"	18			LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
60		298	1 hr.
60		282	4

Temperature of water 53F Depth Artesian Flow Found

Was water analysis done? YES By whom BLUE H2O

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County YAMHILL Lat. ' ' ' Long. ' ' '
Township 3 S Range 3 W WM.
Section 20 NE 1/4 NE 1/4
Tax Lot 101 Lot Block Subdivision
Street Address of Well (or nearest Address)
12001 NE WORDEN HILL RD DUNDRE, OR

(10) STATIC WATER LEVEL:

65 ft. below land surface. Date 05/20/11
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 119
From To Est Flow Rate SWL
119 290 60 65

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
SOIL, W/COBBLES AND BOULDERS	0	6	
SANDSTONE, DECAYED/WX/BROWN, LOOSE	6	17	
SANDSTONE, BROWN DECAY W/SOME GRAY, LOOSE	17	24	
SANDSTONE, MORE GRAY, STILL LOOSE	24	34	
CLAYSTONE, GRAY/BROWN WEATHERED	34	41	
SANDSTONE, HARD GRAY FINE GRAIN	41	88	
CLAYSTONE, DARK GRAY HARD	88	106	
SANDSTONE, HARD GRAY FINE GRAIN	106	218	
SANDSTONE, DK GRAY W/LT GRAY CLAYSTONE	218	239	
SANDSTONE, DK GRAY/GREEN, MED GRAIN	239	252	
SANDSTONE, LT GRAY COARSE GRAIN	252	290	
CLAYSTONE, DK GRAY MED HD W/SHELLS	290	299	

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868 7878

WATER RESOURCES DEPT
SALEM, OREGON

Date started 05/19/11

Completed 05/20/11

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David L. Paysinger* WWC Number 1438
Date 05/22/11

RECEIVED

JUN 15 2011