

YAMH 56074

State of Oregon
 WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L104547
 Start Card # 1014625

(1) OWNER: Well No. 2722
 Name RICHARD CRANWELL
 Address 11280 SE BOLA HILLS RD
 City AMITY St OR Zip 97101

(2) TYPE OF WORK: RECONDITION / *Alteration*
 (3) DRILL METHOD: ROTARY AIR
 (4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
 Special Construction Approval NO _____ Depth of Compl. Well 262 ft
 Explosives used NO _____ Type _____ Amount _____

HOLE		SEAL		Amount
Diam.	From To	Material	From To	

 Seal placement method _____
 Backfill: from _____ ft to _____ ft Material _____
 Gravel: from 60 ft to 262 ft Size 3/8" PEA

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing						
Liner	6	4	262	CL200	PLASTIC	WELDED

 Final Location of shoe(s) BOTTOM OF LINER CAPPED

(7) PERFORATIONS/SCREENS:
 Perf. Method CIRCULAR SAW
 Screens Type _____ Material _____

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
223	261	.1X7"	98			LINER

(8) WELL TESTS: Minimum testing time is 1 hour
 Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
23		260	1 hr.
23		240	1

 Temperature of water 53F Depth Artesian Flow Found _____
 Was water analysis done? NO By whom _____
 Reason for water not suitable for use _____
 Depth of strata _____

(9) LOCATION OF WELL by legal description:
 County YAMHILL Lat. ' ' ' Long. ' ' '
 Township 5 S Range 4 W W.M.
 Section 25 SW 1/4 NE 1/4
 Tax Lot 800 Lot Block Subdivision
 Street Address of Well (or nearest Address)
 11280 SE BOLA HILL RD AMITY, OR

(10) STATIC WATER LEVEL:
 54 ft. below land surface. Date 09/23/11
 Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
 Depth at which water was first found NA

From	To	Est Flow Rate	SWL

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
WORK TO CLEAN, REDEVELOP, INSTALL LINER AND FILTER PACK IN EXISTING WELL.			
SWL 54' BEFORE AND AFTER WORK.			
DAVE PAYSINGER, BLUE WATER DRILLING CO.			
(503) 868 7878			
Date started 09/21/11		Completed 09/23/11	

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
 Signed _____ WWC Number _____
 Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
 Signed *David H. Paysinger* WWC Number 1438
 Date 09/24/11

RECEIVED
 OCT 18 2011
 WATER RESOURCES DEPT
 SALEM, OREGON