

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L107952
Start Card # 1015358

Yamh
56134

(1) OWNER: Well No. 2728
Name DURANT VINEYARDS LLC
Address PO BOX 99
City DUNDEE St OR Zip 97115

(2) TYPE OF WORK: DEEPEN *Alteration*

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 340 ft
Explosives used NO Type Amount

HOLE		SEAL			
Diam.	From To	Material	From To	Amount	
12	0 2	BENTONITE CHIP	0 2	2 SAX	
5.625	169 340				

Seal placement method POURED/HYDRATED

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Diam.	From To	Gauge	Material	Connection
Casing 6	+1.5 2	.25	STEEL	WELDED

Diam.	From To	Gauge	Material	Connection
Liner 4	20 340	SCH40	PLASTIC	THREADED

Final Location of shoe(s) SPLINE-LOC LINER

(7) PERFORATIONS/SCREENS:

[X] Perf. Method CIRCULAR SAW

[] Screens Type

Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
180	200	.1X6	36			LINER
330	340	.1X6	18			LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
9		169	1 hr.
9		340	1

Temperature of water 53F Depth Artesian Flow Found

Was water analysis done? NO By whom

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County YAMHILL Lat. ' ' ' Long. ' ' '
Township 4 S Range 3 W WM.
Section 4 NE 1/4 NE 1/4
Tax Lot 200 Lot Block Subdivision
Street Address of Well (or nearest Address)
5430 NE BREYMAN ORCHARD RD DAYTON, OR

(10) STATIC WATER LEVEL:

117 ft. below land surface. Date 11/14/11
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found	From	To	Est Flow Rate	SWL
169	??	169	9	117

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
DEEPEN AND ADD TERMINAL CASING TO YAMH 5178. NO ADDITIONAL WATER FOUND. SWL BEFORE AND AFTER DEEPENING = 117'			

BASALT, MEDIUM GRAY	169	244
BASALT, MEDIUM GRAY W/SOME BROWN	244	263
BASALT, MEDIUM GRAY	263	277
BASALT, MEDIUM GRAY W/SOME BROWN	277	328
BASALT, MEDIUM GRAY	328	340

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868 7878

Date started 11/11/11 Completed 11/14/11

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David Paysinger* WWC Number 1438
Date 11/14/11

RECEIVED
DEC 08 2011
WATER RESOURCES DEPT
SALEM, OREGON

RECEIVED



Submitted voluntarily by Joshua Teamus at ODA with GPS coordinates

RECEIVED

DEC 11 2025

OWRD