

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

RECEIVED  
YAMH 5660  
DEC 24 1987

YAMH  
5660

4s/4w-11ac

(1) OWNER: Stanley Hermens  
Name: Stanley Hermens  
Address: 3361 S.E. ST. Joseph Rd.  
City: McMinnville State: Ore. Zip: 97128

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval Yes No  Depth of Completed Well 90 ft.  
Explosives used  Yes  No  Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE SEAL Amount  
Diameter From To Material From To sacks or pounds  
13 0 91 Cement 0 26 28 SACKS

How was seal placed: Method  A  B  C  D  E  
 Other \_\_\_\_\_  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from 26 ft. to 90 ft. Size of gravel 7/8 pea

(6) CASING/LINER:  
Diameter From To Gauge Steel Plastic Welded Threaded  
Casing: 6 +1 89 .25      
Liner:      
Final location of shoe(s) \_\_\_\_\_

(7) PERFORATIONS/SCREENS:  
 Perforations Method Torch  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_  
From To Slot size Number Diameter Tele/pipe size Casing Liner  
74 89 50 1 1/4 x 12

(8) WELL TESTS: Minimum testing time is 1 hour  
 Pump  Bailer  Air  Flowing Artesian  
Yield gal/min Drawdown Drill stem at Time  
60+ 55 90 6hr.

Temperature of water 53 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Yamhill Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 4S N or S, Range 4W E or W, WM.  
Section 11 SW 1/4 NE 1/4  
Tax Lot \_\_\_\_\_ Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) SAME

(10) STATIC WATER LEVEL:  
35 ft. below land surface. Date Dec. 14, 87  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 70  
From To Estimated Flow Rate SWL  
70 89 60

(12) WELL LOG: Ground elevation 175 ft.  
Material From To SWL  
Topsoil 0 2  
Brown Clay 2 17  
Blue clay 17 46  
Silty Blue clay 46 53  
Silty Brown + Blue Clay 53 70  
Med of Fine Blue Sand w/ small Blue Gravel 70 89  
Soft gray Shale 89 91

Date started Dec 9 87 Completed Dec 14 87

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed Not Appl. WWC Number \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
Signed James H. Wilcox WWC Number 428 Date Dec. 14 87

# YAMH 5660



Oregon Water Resources Department  
725 Summer Street NE, Suite A  
Salem Oregon 97301  
(503) 986-0900  
www.oregon.gov/owrd

## Application for Well ID Number

RECEIVED

JUN 21 2022

Do not complete if the well already has a Well Identification Number.

OWRD

### I. OWNER INFORMATION

Current Owner Name (please print): North American Plants Inc. c/o Yongjian Chang

Mailing Address: 9375 SE Warmington Rd

City, State, Zip: McMinnville, OR 97128

Mail Well ID to:  SAME AS ABOVE  In Care Of (C/O)

Name & Address: \_\_\_\_\_

City, State, Zip: \_\_\_\_\_

### II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 4S (North / South) Range: 4W (East / West) Section: 11 NE 1/4 of the SE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 5400 County Yamhill

GPS Coordinates: 45.23455800, -123.14038600

Street Address of Well, City: 9375 SE Warmington Rd, McMinnville, OR 97128

If the property had a different street address in the past: \_\_\_\_\_

### III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Per well log - Domestic

Date Well Constructed (or property built): 12-14-1987 Total Well Depth: 91' Casing Diameter: 6 inch

Owner at time the well was constructed (if known): Stanley Hermens Well Report # (if known): YAMH 5660

Other Information: Per Permit G-15352 submitted by client - this is the well log for the approved well 1.

SUBMITTED BY (please print): Yongjian Chang, North American Plants, Inc.

PHONE: 503 474 1852 EMAIL &/or FAX: 503 474 0872

To send the completed application, you may MAIL it to: Oregon Water Resources Dept. 725 Summer St NE, Suite A, Salem, Oregon 97301.  
Or EMAIL the completed PDF form to: Ladeena.K.Ashley@water.oregon.gov, or FAX it to: (503) 986-0902.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

6-21-22

Well Report Number:

YAMH 5660

Well Identification #:

L 146924