

YAMH 56783

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L112372
Start Card # 1022520

(1) OWNER: Well No. 2832
Name CARLTON NURSERY CO LLC
Address POB 398
City DAYTON St OR Zip 97114

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 78 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
13 0 24 BENTONITE CHIP 0 24 33 SAX
10 24 78

Seal placement method POURED/PROBED
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 8 +2 78 .25 STEEL WELDED

Liner
Final Location of shoe(s)

(7) PERFORATIONS/SCREENS:
 Perf. Method DH PERFORATOR
 Screens Type Material
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
56 71 .2X1" 124 CASING

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
300 75 1 hr.
300 75 8
Temperature of water 54F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ° ' " Long. ° ' "
Township 5 S Range 3 W WM.
Section 33 NW 1/4 NE 1/4
Tax Lot 100 Lot Block Subdivision
Street Address of Well (or nearest Address):
21811 SE WALLACE RD DAYTON, OR

(10) STATIC WATER LEVEL:
10 ft. below land surface. Date 03/20/14
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 10
From To Est Flow Rate SWL
10 78 300 10

(12) WELL LOG:
Material Ground elevation From To SWL
SILTY TOP SOIL 0 6
CLAY, BROWN/SILTY 6 24
SAND & GRAVEL, BOTH FINE TO MED, BROWN 24 32
SAND & GRAVEL, BOTH FINE TO MED, BLACK 32 41
SAND, MED & GRAVEL FINE TO MED, GRAY 41 70
CLAY, GRAY 70 78

RECEIVED BY OWRD

MAY 09 2014

DAVE PAYSINGER, bluewaterdrilling.com
(503) 868 7878 SALEM, OR

Date started 03/18/14 Completed 03/20/14

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David M. Paysinger* WWC Number 1438
Date 03/20/14