

STATE OF OREGON
WATER SUPPLY WELL REPORT

YAMH 59181

WELL I.D. LABEL# L 147371
START CARD # 1059753
ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

2/20/2023

(1) LAND OWNER Owner Well I.D. REED IRRIGATION WELL
First Name _____ Last Name _____
Company ROBINSON FARMS LLC
Address PO BOX 100
City AMITY State OR Zip 97101

(2) TYPE OF WORK New Well Deepening Conversion
 Alteration (complete 2a & 10) Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrd
Casing: _____
Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable Auger Cable Mud
 Reverse Rotary Other _____

(4) PROPOSED USE Domestic Irrigation Community
 Industrial/ Commercial Livestock Dewatering
 Thermal Injection Other _____

(5) BORE HOLE CONSTRUCTION Special Standard (Attach copy)
Depth of Completed Well 107.50 ft.
BORE HOLE
Dia From To Material From To Amt sacks/lbs
12 0 107.5 Bentonite Chips 0 22 27 S
Calculated 12.48
Cement with 2% Bento 22 50 35 S
Calculated 8.05

How was seal placed: Method A B C D E
 Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Filter pack from 50 ft. to 107.5 ft. Material SILICA SAND Size 8-12
Explosives used: Yes Type _____ Amount _____

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount _____ Actual Amount _____

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd
 8 2 78 .250
 8 98 107.5 .250
Shoe Inside Outside Other Location of shoe(s) _____
Temp casing Yes Dia 12 From + 0 To 107

(7) PERFORATIONS/SCREENS
Perforations Method _____
Screens Type v-wire Material stainless
Perf/ Casing/ Screen Dia From To Scrn/slot Slot # of Tele/
Screen Liner Dia From To width length slots pipe size
Screen Casing 8 78 98 .04 _____ 8 _____

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
35 _____ 52 4
Temperature 54 °F Lab analysis Yes By _____
Water quality concerns? Yes (describe below) TDS amount 264 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County YAMHILL Twp 5.00 S N/S Range 4.00 W E/W WM
Sec 7 SE 1/4 of the NE 1/4 Tax Lot 100
Tax Map Number _____ Lot _____
Lat _____ " or 45.15323300 DMS or DD
Long _____ " or -123.21967700 DMS or DD
 Street address of well Nearest address
9000 SW RIVERBEND ROAD MCMINNVILLE, OR 97128

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration _____
Completed Well 2/15/2023 _____ 14.3
Flowing Artesian? Dry Hole?
WATER BEARING ZONES Depth water was first found 63.00
SWL Date From To Est Flow SWL(psi) + SWL(ft)
1/15/2023 63 98 160 _____ 19.42

(11) WELL LOG Ground Elevation _____

Material	From	To
clay brwn silty soft	0	17
clay brwn soft	17	25
sand brwn coarse to fine soft	25	31
clay gray sandy gritty soft	31	35
clay gray sandy soft	35	37
clay gray sandy silty	37	44
clay gray silty soft some green	44	63
sand coarse blk w/small gravels	63	68
sand coarse fine to coarse silty	68	77
gravel small sand blk fine	77	82
gravel coarse well rounded sand coarse	82	90
to fine	82	90
sand coarse fine pea gravel silty	90	95
wood w/silty sand coarse	95	98
sand coarse silty	98	104
sandstone blk harder	104	107.5

Date Started 1/13/2023 Completed 2/15/2023

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number _____ Date _____
Signed _____

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1483 Date 2/20/2023
Signed JOHN STADELI (E-filed)
Contact Info (optional) Arrow Drilling 503-538-4422

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

YAMH 59181

2/20/2023

Map of Hole

**STATE OF OREGON
WELL LOCATION MAP**

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department
725 Summer St NE, Salem OR 97301
(503)986-0900



Well Label: 147371
Printed: February 20, 2023

LOCATION OF WELL
Latitude: 45.15323300 Datum: WGS84
Longitude: -123.21967700
Township/Range/Section/Quarter-Quarter Section:
WM5.00S4.00W7SENE
Address of Well:
9000 SW RIVERBEND ROAD MCMINNVILLE, OR 97128

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.
Provided by well constructor

