

STATE OF OREGON
WATER SUPPLY WELL REPORT

YAMH 59914

WELL I.D. LABEL# L

159782

START CARD #

1082583

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/10/2026

(1) LAND OWNER

Owner Well I.D. 26-19

First Name PIPER

Last Name UNDERBRINK

Company PRIVE PROPERTIES LLC

Address 28155 NE BELL RD

City NEWBERG

State OR

Zip 97132

(2) TYPE OF WORK☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Reverse Rotary ☐ Other _____**(4) PROPOSED USE**☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other _____**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)

Depth of Completed Well 322.00 ft.

BORE HOLE				SEAL			sacks/
Dia	From	To	Material	From	To	Amt	lbs
10	0	130	Bentonite Chips	0	67	65	S
6	130	322			Calculated	30.58	
			Cement with 2% Bento	67	130	20	S
					Calculated	14.58	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: BENT POURED-PROBE

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 7/6/2026 Begin Time 11 30

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	2	130	0.250	ST	☒		OUT.	130
L	4.5		21	322	Sch40	PL		☒		

Temp casing ☒ Yes Dia 10 From + ☐ 0 To 73**(7) PERFORATIONS/SCREENS**

Perforations Method _____

Screens Type slotted Material PVC

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Liner	4.5	222	242	.032			Pipe Size
Screen	Liner	4.5	282	322	.032			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	7		320	1

Temperature 54 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 71 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County YAMHILL Twp 2.00 S N/S Range 3.00 W E/W WM

Sec 33 NW 1/4 of the NW 1/4 Tax Lot 1000

Tax Map Number _____ Lot _____

Lat _____ " or 45.35910900 DMS or DD

Long _____ " or -123.06929293 DMS or DD

☒ Street address of well ☐ Nearest address

19500 NE RIBBON RIDGE RD NEWBERG, OR 97132

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/6/2026			55.3
Flowing Artesian? ☐ Dry Hole? ☐				

WATER BEARING ZONES

Depth water was first found 56.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/6/2026	56	68	1			21
7/6/2026	225	304	7			55.3

(11) WELL LOG

Ground Elevation 528.44 FT

Material	From	To
top soil	0	1
clay brwn stiff	1	23
sandstone very soft brwn wthd	23	41
sandstone very soft yellow	41	56
clay gray sandy soft	56	68
sandstone gray fine soft	68	92
sandstone brwn soft	92	98
sandstone gray fine soft	98	110
sandstone gray med-firm	110	141
sandstone gray prog firmer	141	190
sandstone gray med w/mica flakes	190	225
shale/claystone gry firm w/hrd lenses occ sm frac	225	304
shale brwn firm w/occ hrd lense	304	322

Construction

Begin Date 6/29/2026 Begin Time 07 47 End Date 7/6/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1483 Date 7/10/2026

Signed JOHN STADELI (E-filed)

Drilling Company: Arrow Drilling 503-538-4422

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

Comments/Remarks

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

YAMH 59914

7/10/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.35910900 Datum: WGS84

Longitude: -123.06929293

Township/Range/Section/Quarter-Quarter Section:
WM2.00S3.00W33NWNW

Address of Well:

19500 NE RIBBON RIDGE RD NEWBERG, OR 97132

Well Label: 159782

Printed: July 9, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

