

STATE OF OREGON
WATER SUPPLY WELL REPORT

YAMH 59916

WELL I.D. LABEL# L

Page 1 of 3

START CARD #

1082651

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/22/2026

(1) LAND OWNER

Owner Well I.D. 26-21-1

First Name JULIE

Last Name COLES

Company ROCKYFORD YAMHILL 2 LLC

Address PO BOX 82106

City BAKERSFIELD State CA Zip 93380

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☒ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☐ Domestic ☒ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 0.00 ft.

BORE HOLE			SEAL			Amt	sacks/ lbs
Dia	From	To	Material	From	To		
10	0	6	Other	0	1	10	P
6	6	402	Calculated				
			Bentonite Chips	1	402	112	S
			Calculated				

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: BENT POURED-PROBE

Backfill placed from 0 ft. to 1 ft. Material CLEAN DIRT

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 7/9/2026 Begin Time 15 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount 107.00 Sacks Actual Amount 112.00 Sacks

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)

Temperature 54 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County YAMHILL Twp 3.00 S N/S Range 5.00 W E/W WM

Sec 1 SW 1/4 of the SW 1/4 Tax Lot 2300

Tax Map Number Lot

Lat ° ' " or 45.33460000 DMS or DD

Long ° ' " or -123.25759000 DMS or DD

☒ Street address of well ☐ Nearest address

16735 NW ROCKYFORD RD YAMHILL, OR 97148

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well				
Flowing Artesian? ☐ Dry Hole? ☐				

WATER BEARING ZONES

Depth water was first found

SWL Date From To Est Flow SWL (psi) + SWL (ft)

7/9/2026	29	119	2		34
7/9/2026	317	349	0.5		317

(11) WELL LOG

Ground Elevation 587.45 FT

Material	From	To
top soil	0	1
clay brwn firm	1	5
shale brwn red gray wthd & seamy	5	13
shale gray firm	13	21
shale gray soft	21	29
shale charcoal gray med-sft clayey	29	75
shale gray soft less clayey & firmer	75	119
shale/claystone gray firm	119	143
shale gray soft	143	205
shale charcoal gray med w/lgt gray	205	295
claystone/sandstone cong hrd gray	295	317
siltstone gray firm occ brwn to brwn	317	349
marine rock gray med-hrd	349	402

Construction

Begin Date 7/8/2026 Begin Time 08 00 End Date 7/9/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1483 Date 7/22/2026

Signed JOHN STADELI (E-filed)

Drilling Company: Arrow Drilling 503-538-4422

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

YAMH 59916

7/22/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.33460000 Datum: WGS84

Longitude: -123.25759000

Township/Range/Section/Quarter-Quarter Section:
WM3.00S5.00W1SWSW

Address of Well:

16735 NW ROCKYFORD RD YAMHILL, OR 97148

Hole Nbr: 26-21-1

Printed: July 22, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

