

RECEIVED

YAMH 6404 6404

55/3W-7ac
3890

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

APR 13 1988

(1) OWNER:

Name Montevia Nursing Home
Address PO Box 562 Dayton Ore
City Dayton State Ore Zip 97114

(2) TYPE OF WORK:

New Well Deepen Recondition Abandon

(3) DRILL METHOD

Rotary Air Rotary Mud Cable
 Other

(4) PROPOSED USE:

Domestic Community Industrial Irrigation
 Thermal Injection Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well 121 ft.
Explosives used Yes No Type _____ Amount _____

HOLE		SEAL		Amount
Diameter	From To	Material	From To	sacks or pounds
10"	0 121	Cement	0 18	15

How was seal placed: Method A B C D E
 Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 18 ft. to 121 ft. Size of gravel 3/8" P

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	12	121	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

Perforations Method TORCH
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
46	53	1/4x6	28			<input checked="" type="checkbox"/>	<input type="checkbox"/>
95	100	11	20			<input checked="" type="checkbox"/>	<input type="checkbox"/>
110	116	11	24			<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
33		120	1 hr.
33		120	7HR

Temperature of water _____ Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Washburn Latitude _____ Longitude _____
Township 55 N or S, Range 3W E or W, WM.
Section 7 SW 1/4 NE 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 13000 Alderman Rd Dayton Ore

(10) STATIC WATER LEVEL:

9 ft. below land surface. Date 4/8/88
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

From	To	Estimated Flow Rate	SWL
46	51	15	
95	100	15	
109	117	3	9

(12) WELL LOG:

Material	From	To	SWL
Blue Clay	0	3	
Gray Clay	3	10	
Blue Clay	10	21	
Brown Clay	21	30	
Gray Clay	30	46	
Green Clay w/Fine sand/Gravel	46	51	✓
Blue Clay	51	73	
Green Clay	73	95	
Brown Clay w/Fine Black Sand	95	100	✓
Green Clay	100	109	
Red/Brown Claystone - Soft	109	117	✓
Red/Brown Clay	117	121	

Date started 4/4/88 Completed 4/8/88

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed David H. Payinger WWC Number 1438
Date 4/8/88

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Robert Schelburne WWC Number 417
Date 4/8/88

RECEIVED

YAMH 6404

No 3890

APR 05 1988

"START CARD"

WATER RESOURCES DEPT. NOTICE OF BEGINNING OF WELL CONSTRUCTION
SALEM, OREGON (as required by ORS 537.762)

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and Mailing Address Monrovia Nutsey One.
PO Box 562 Dayton Ore

Proposed Commencement Date April 4 1988

Proposed Well Depth 120, Diameter 6
and Use:
 Domestic Community Industrial Irrigation
 Thermal Injection Other

Proposed Well Location: County Yamhill
Township 5 S (N or S) Range 3 W (E or W) Section 7

At least 2 of these must be provided

1. SW 1/4 of NE 1/4 of above section
2. street address of 13000 Alderman Rd Dayton Ore
well location _____
3. tax lot number of well location _____
4. attach approved map with location identified.
(see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

X _____
Owner's Signature

Title

Date

x Robert Schellburne
Bonded Water Well Constructor
License No. 417
Company Blue Water Drilling

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.