

WATER WELL REPORT
STATE OF OREGON

YAMH

RECEIVED

MAY 1 1984

State Well No.

55/bw-36cb

WATER RESOURCES DEPT

State Permit No.

SALEM, OREGON

7649

PLEASE TYPE or PRINT

(1) OWNER:

Name Mrs. E. EVANS
Address RR 1
City Sheridan State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal: ☐ Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☐
6" Diam. from +1 ft. to 23 ft. Gauge 25
" Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

4" Diam. from 15 ft. to 155 ft. Gauge 160 P.V.C.

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Electric Drill
Size of perforations 5/8 Circular in.
150 perforations from 115 ft. to 155 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
d: gal./min. with ft. drawdown after hrs.
" " " " " "
Air test 3 1/2 gal./min. with drill stem at 155 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 53 Depth artesian flow encountered ft.

(10) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement Grout
Well sealed from land surface to 23 ft.
Diameter of well bore to bottom of seal 10 1/2 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 7 1/2 sacks
How was cement grout placed? Hole was blown clean & dry cement grout introduced from bottom upward
Was pump installed? ☒ No Type HP Depth ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Yamhill Driller's well number
NW 1/4 Sec 36 T. 53 R. 6W W.M.
Tax Lot # 56-36-2800 Lot Blk Subdivision
Address at well location: SAME

(12) WATER LEVEL: Completed well.

Depth at which water was first found 131 ft.
Static level ft. below land surface. Date 4/25/84
Artesian pressure lbs. per square inch. Date

(13) WELL LOG:

Diameter of well below casing 6"

Depth drilled 135 ft. Depth of completed well 155 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	1	
Brown Clay	1	9	
Brown & yellow decomposed clay	9	13	
Brown & blue med. gravels	13	17	
Firm Gray Shale w/ unstable layers	17	155	

Work started 4-19 1984 Completed 4-25 1984
Date well drilling machine moved off of well 4-25 1984

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] _____ Date _____, 19____

Bonded Water Well Constructor Certification:

Bond 28046279 Issued by: Western Surety
(number) Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name WILLCOX DRILLING & PUMP CO.
(Person, firm or corporation) (Type or print)

Address P.O. Box 589 McMinnville, Ore.

[Signed] Randall J. Wilcox
Water Well Constructor Date 4/26, 1984

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*45292-690