

16

VAMH
7931

RECEIVED

SEP 13 1995

055/05W/204C

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1 Start Card # 78655

(1) OWNER: Well No. 1544
Name ERIC LEMELSON
Address 29001 SW HEATER RD
City SHERWOOD St OR Zip 97140

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval: NO
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
10 0 66 BENTONITE 0 48 12 SAX
6 66 240 CEMENT W/GEL 48 66 4 SAX

Seal placement method C
Backfill: from ft to ft Material
Gravel: from ft to ft Size

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +2 66 .25 STEEL WELDED
Liner
Final Location of shoe(s) NO SHOE

(7) PERFORATIONS/SCREENS:
[] Perforations Method
[] Screens Type Material
Slot Tele/pipe
From To Size Number Diam. size Casing/liner

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
1 240 1 hr.
Temperature of water 55 Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata 0

(9) LOCATION OF WELL by legal description:
SALEM OREGON
County YAMHILL Lat. 45° 07' 53" Long. 123° 19' 49"
Township 5 S Range 5 W WM.
Section 20 SW 1/4 NE 1/4
Tax Lot 5520 Lot 300 Block Subdivision
Street Address of Well (or nearest Address)
18600 MUDDY VALLEY RD , OR

(10) STATIC WATER LEVEL:
95 ft. below land surface. Date 09/07/95
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 187
From To Est Flow Rate SWL
187 188 1 95

(12) WELL LOG:
Material Ground elevation
From To SWL
FILL 0 2
RED CLAY 2 19
BROWN CLAY 19 41
BROWN SANDY CLAY 41 47
MARINE ROCK, GRAY 47 49
BROWN CLAY 49 54
HARD GRAY MARINE ROCK 54 187
MARINE ROCK/CLAYSTONE MIX 187 188 95
CLAYSTONE W/SOME MARINE ROCK PARTICLES 188 240

DAVE PAYSINGER
BLUE WATER DRILLING CO.
DAYTON, OR. 97114

Date started 09/06/95 Completed 09/07/95

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David S. Paysinger* WWC Number 1438
Date 09/07/95