

16

VAMH
1933

RECEIVED

SEP 13 1995

055/05W/201AB

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

WATER RESOURCES DEPT.

Start Card # 78656

(1) OWNER: Well No. 1545 #2
Name ERIC LEMELSON
Address 29001 SW HEATER RD
City SHERWOOD St OR Zip 97140

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval: NO Depth of Compl. Well 120 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
10 0 18 BENTONITE 0 18 7 SAX
6 18 120

(9) LOCATION OF WELL by legal description:
County YAMHILL Lat. ' ' ' Long. ' ' '
Township 5 S Range 5 W WM.
Section 20 SW 1/4 NE 1/4
Tax Lot 5520 Lot 300 Block Subdivision
Street Address of Well (or nearest Address)
18600 MUDDY VALLEY RD , OR #2

(10) STATIC WATER LEVEL:
35 ft. below land surface. Date 09/07/95
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 91
From To Est Flow Rate SWL
91 109 12 35

Seal placement method POURED/TAMPED
Backfill: from ft to ft Material
Gravel: from ft to ft Size

(12) WELL LOG:
Material Ground elevation
From To SWL
RED CLAY 0 2
BROWN CLAY 2 9
HARD GRAY MARINE ROCK 9 91
BROKEN MARINE ROCK, COARSE GRAINED 91 109 35
HARD GRAY MARINE ROCK 109 120

DAVE PAYSINGER
BLUE WATER DRILLING CO.
DAYTON, OR. 97114

Date started 09/07/95 Completed 09/07/95

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +2 18 .25 STEEL WELDED

Liner 4 0 120 SDR26 PLASTIC WELDED
Final Location of shoe(s) NO SHOE

(7) PERFORATIONS/SCREENS:
 Perforations Method ELECTRIC SAW
 Screens Type Material
Slot Tele/pipe
From To Size Number Diam. size Casing/liner
100 120 6" 36 LINER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
12 120 1 hr.

Temperature of water 54 Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata 0

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David S. Payne* WWC Number 1438
Date 09/07/95